



02054531

PETROLEUM DEVELOPMENT CORPORATION

State Contact: David Andrews david.andrews@state.co.us

WELL NAME PUCKETT 21D-24D

DATE 09/08/2010

API# 05-045-16110

LEASE#

PERMIT #

CASING AND HOLE INFORMATION

DEPTH HOLE 2320
CASING 9 5/8 36#, 8RD, ST&C
DEPTH SET 2309

Cement report

Company : BJ

CASING STRING:


LEAD: (35:65) Type III plus additives 1494 sacks 12.5 ppg 1.95 yld 518 bbl slurry mixed @ 4.7/3.5 bbl/min

TAIL: TYPE III plus additives 170 sacks 14.2 ppg 1.47 yld 38.77 bbl slurry mixed @ 3.5 bbl /min

DISPLACED Displaced w/ 174 bbls water @6.9 Dwn To 2.44 bbl/min bumped plug w/ 1117 psi Float held no cement to surface.
PRESSURE BEFORE BUMPING PLUG: 181. plug bumped at 1117

RETURN: No Returns.

COMENTS: Toped Out cement= 1136 sks. Cement to surface and did not fall back.
Type III cement with additives, 14.2# and 1.61 yield 326 bbls slurry.



Any Questions or problems please advise

Gene Sandefer
970-260-0587