

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

 OIL ☐ GAS ☒ COALBED ☐ OTHER _____
 SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐
Refiling ☐Sidetrack ☐

Document Number:

400091000

Plugging Bond Surety

20060137

3. Name of Operator: OXY USA WTP LP4. COGCC Operator Number: 665715. Address: P O BOX 27757City: HOUSTON State: TX Zip: 772276. Contact Name: Joan Proulx Phone: (970)263.3641 Fax: (970)263.3694Email: joan_proulx@oxy.com7. Well Name: Cascade Creek Well Number: 697-08-27B

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 9095

WELL LOCATION INFORMATION

10. QtrQtr: NWSE Sec: 8 Twp: 6S Rng: 97W Meridian: 6Latitude: 39.533973 Longitude: -108.241801
 Footage at Surface: 1377 FNL/FSL FSL 2157 FEL/FWL FEL
11. Field Name: Brush Creek Field Number: 756212. Ground Elevation: 8382 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 09/01/2010 PDOP Reading: 0.9 Instrument Operator's Name: James Seal15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL 2635 FNL 1606 FWL 2567 FNL 1524 FWL
 Bottom Hole: FNL/FSL 2567 FNL 1524 FWL
 Sec: 8 Twp: 6S Rng: 97W Sec: 8 Twp: 6S Rng: 97W
16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 4544 ft18. Distance to nearest property line: 3134 ft 19. Distance to nearest well permitted/completed in the same formation: 281 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	510-15		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached Mineral Lease Description

25. Distance to Nearest Mineral Lease Line: 3057 ft 26. Total Acres in Lease: 9480

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20+0/0	16+0/0	65	90	4	90	0
SURF	14+3/4	9+5/8	36	2,690	1,420	2,690	0
1ST	8+3/4	4+1/2	11.6	9,086	1,900	9,086	5,741

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Oxy is both the surface and mineral owner; Rules 305 and 306 are waived . The well pad has been constructed and there is one producing well on this location. A semi-closed loop system will be used. Per GarCo Vacation Ordinance dated 10-5-1987, CR 213 is now OXY's private property north of Sec 8, 7S, 97W, 6 PM. Oxy will provide appropriate housing for essential personnel in order to conduct safe, efficient drilling operations at this well site.

34. Location ID: 335815

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Joan Proulx

Title: Regulatory Analyst Date: 9/8/2010 Email: joan_proulx@oxy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Permit Number: _____ Expiration Date: _____

API NUMBER

05

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name	Doc Description
400091000	FORM 2 SUBMITTED	400091000.pdf
400091003	MINERAL LEASE MAP	Mineral lease description.PDF
400091005	DEVIATED DRILLING PLAN	CC 697-08-27B Plan 1.pdf
400091006	TOPO MAP	697-08-53 Reference.pdf
400091007	WELL LOCATION PLAT	img-908102416-0001.pdf

Total Attach: 5 Files