



02054538

PETROLEUM DEVELOPMENT CORPORATION

State Contact: David Andrews david.andrews@state.co.us

WELL NAME PUCKETT 21C-24D

DATE 09/13/2010

API# 05-045-16109-00

LEASE# 636800

PERMIT # 20080535

CASING AND HOLE INFORMATION

DEPTH HOLE 2611'

CASING 9 5/8 36#, 8rD, ST&C

DEPTH SET 2596'

Cement report

Company : BJ

CASING STRING:

LEAD: PREMLITEHS35/65 plus additives 1494 sacks 12.5 ppg 1.95 yld 520bbl slurry mixed @ 6.5 bbl/min

TAIL: TYPE III plus additives 170 sacks 14.2 ppg 1.47 yld 44.5 bbl slurry mixed @ 7.9 bbl/min

DISPLACED Displaced w/ 206 bbls water @ 7.9 Dwn To 2.5 bbl/min bumped plug w/ 1220 psi Float held No cement to surface.

PRESSURE BEFORE BUMPING PLUG: 221 psi., plug bumped at 1220 psi.

RETURN: No Returns.

COMMENTS:

Topped Surface casing with 554 sks cement, dropped 10 feet and topped Out to surface and Held. All Good.

Top Out Cement= 554 sks. Type III plus additives.

14.2# Yield 1.47, Slurry 145 water 99 bbls.

RECEIVED

SEP 13 2010

COGCC

Any Questions or problems please advise

Gene Sandefer
970-260-0587