

**FORM
5**Rev
02/08State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400092848

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☐ Final completion ☒ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: Kenny Trueax

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6383

3. Address: P O BOX 173779

Fax: (720) 929-7383

City: DENVER State: CO Zip: 80217-37

5. API Number 05-123-30959-00

6. County: WELD

7. Well Name: NORTHGLENN STATE

Well Number: 5-36

8. Location: QtrQtr: SWNE Section: 36 Township: 1N Range: 68W Meridian: 6

Footage at surface: Direction: FNL Distance: 2484 Direction: FEL Distance: 2488

As Drilled Latitude: As Drilled Longitude:

GPS Data:

Data of Measurement: PDOP Reading: GPS Instrument Operator's Name:

** If directional footage

at Top of Prod. Zone Distance: 1979 Direction: FNL Distance: 4634 Direction: FEL

Sec: 36 Twp: 1N Rng: 68W

at Bottom Hole Distance: 1996 Direction: FNL Distance: 4601 Direction: FEL

Sec: 36 Twp: 1N Rng: 68W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number: 70/8571-S

12. Spud Date: (when the 1st bit hit the dirt) 08/17/2010 13. Date TD: 08/20/2010 14. Date Casing Set or D&A: 08/21/2010

15. Well Classification:

☐ Dry ☐ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 9017 TVD 8539 17 Plug Back Total Depth MD 6502 TVD 6024

18. Elevations GR 4934 KB 4949

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

Preliminary Form 5

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24#	1,085	680	1,085	0
1ST	7+7/8	4+1/2	11.6#	9,008	1,115	9,008	985

ADDITIONAL CEMENT

Cement work date: _____

Details of work: _____

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	4,834		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	5,265		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	8,010		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	8,415		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	8,440		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	8,867		<input type="checkbox"/>	<input type="checkbox"/>	

Comment: _____

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kenny Trueax

Title: Regulatory Analyst II Date: _____ Email: kenny.trueax@anadarko.com

Based on the information provided herein, this Drilling Completion Report (Form 5) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Attachment Check List

Att Doc Num	Name	Doc Description
400092864	DIRECTIONAL SURVEY	KERR MCGEE NORTHGLENN STATE 5-36 Final Plot & Survey (09.02.10).pdf
400092865	CMT SUMMARY	NORTHGLENN ST 5-36 SURF CMT TKT.PDF

Total Attach: 2 Files