

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐
Sidetrack ☐

Document Number:

400074843

Plugging Bond Surety

20040060

3. Name of Operator: BARRETT CORPORATION* BILL

4. COGCC Operator Number: 10071

5. Address: 1099 18TH ST STE 2300

City: DENVER State: CO Zip: 80202

6. Contact Name: Elaine Winick Phone: (303)312-8168 Fax: (303)291-0420
Email: ewinick@billbarrettcorp.com

7. Well Name: Kaufman Well Number: 21B-24-692

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7671

WELL LOCATION INFORMATION

10. QtrQtr: SWNE Sec: 24 Twp: 6S Rng: 92W Meridian: 6

Latitude: 39.516061 Longitude: -107.614297

Footage at Surface: 1419 FNL/FSL FNL 2279 FEL/FWL FEL

11. Field Name: Mamm Creek Field Number: 52500

12. Ground Elevation: 5771.5 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 05/21/2010 PDOP Reading: 6.0 Instrument Operator's Name: Jim Kalmon

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 856 FNL 1958 FWL 856 FNL 1958 FWL
Sec: 24 Twp: 6S Rng: 92W Sec: 24 Twp: 6S Rng: 92W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 881 ft

18. Distance to nearest property line: 107 ft 19. Distance to nearest well permitted/completed in the same formation: 331 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williamfork-lles	WFILS	191-64	320	W/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached lease map.

25. Distance to Nearest Mineral Lease Line: 680 ft 26. Total Acres in Lease: 2226

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Evaporation and Backfill

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	16	42#	40	0	40	0
SURF	12+1/4	9+5/8	36#	770	240	770	0
1ST	7+7/8	4+1/2	11.6#	7,671	550	7,671	4,551

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments On Kaufman 6 pad. Rule 305 and 306 have been waived. See attached surface use agreement.

34. Location ID: 418772

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Elaine Winick

Title: Senior Permit Analyst Date: 7/6/2010 Email: ewinick@billbarrettcorp.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 9/17/2010

API NUMBER

05 045 19920 00

Permit Number: _____ Expiration Date: 9/16/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

4) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 570 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400074843	FORM 2 SUBMITTED	LF@2522852 400074843
400074851	OTHER	LF@2522853 400074851
400074852	PLAT	LF@2522854 400074852
400074854	MULTI-WELL PLAN	LF@2522855 400074854
400074856	MINERAL LEASE MAP	LF@2522856 400074856
400074857	SURFACE AGRMT/SURETY	LF@2522857 400074857
400074858	TOPO MAP	LF@2522858 400074858
400074859	DEVIATED DRILLING PLAN	LF@2522859 400074859
400084287	EXCEPTION LOC WAIVERS	LF@2522860 400084287
400084288	EXCEPTION LOC REQUEST	LF@2522861 400084288
400084289	PROPOSED BMPs	LF@2522862 400084289

Total Attach: 11 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Added location number 418772 for approved form 2A per EW.	9/13/2010 9:54:07 AM

Total: 1 comment(s)

Error: Subreport could not be shown.