

## Present Status Diagram

**Present Status:** Producing well

API No: 05-075-07156  
 Operator: East Cheyenne Gas Storage  
 Well Name: Kenneth Gillham No 3  
 Field Name: West Peetz  
 Location: 2310 FSL 2310 FWL  
 NE SW Sec 6 T11N R52W  
 Logan County, Colorado

Total Depth: 5340 ft  
 Completion Date: 22-Jun-52  
 Hole Size: 13-5/8 to 216 ft  
 9-1/2 to 5333

Surface Casing: 216' 9-5/8" 25.4 lb casing  
 w/175 sacks cemented to surface

Production Casing: 5339' 5-1/2 15.5 lb 8 Rd J-55  
 Cememeted w/250 sacks w/Baker shoe

Perforation Detail:	Formation	Top	Bottom	Shots	
	J Sandstone	5288	5294	4	
	J Sandstone	5299	5305	4	
	D Sandstone	5175	5180	4	Squeezed
	D Sandstone	5176	5180	4	

Completion Detail:	Injection Well	
Tubing - 2-3/8" 4.7 lb. J-55 EUE to 5288.25'		5/24/1993
Tubing - 2-3/8" 4.7 lb. J-55 EUE to 5288.25'		9/25/1993
Tubing - 2-3/8" 4.7 lb. J-55 EUE to 5288.25'		12/12/1993

Formation Tops:		
D Sandstone		5144 ft
J Sandstone		5274 ft

