

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

 OIL GAS COALBED OTHER _____
 SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE
Refiling Sidetrack

Document Number:

400084124

Plugging Bond Surety

20030009

3. Name of Operator: NOBLE ENERGY INC 4. COGCC Operator Number: 1003225. Address: 1625 BROADWAY STE 2200City: DENVER State: CO Zip: 802026. Contact Name: Tania McNutt Phone: (303)228-4392 Fax: (303)228-4286Email: tmcnutt@nobleenergyinc.com7. Well Name: Double B Ranch Well Number: 18-44B (17M)

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 10288

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 17 Twp: 7S Rng: 94W Meridian: 6Latitude: 39.433399 Longitude: -107.917789Footage at Surface: 605 FNL/FSL FSL 476 FEL/FWL FWL11. Field Name: Rulison Field Number: 7540012. Ground Elevation: 7558.4 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 06/23/2008 PDOP Reading: 2.3 Instrument Operator's Name: John Richardson15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

850 FSL 613 FEL 850 FSL 613 FELSec: 18 Twp: 7S Rng: 94W Sec: 18 Twp: 7S Rng: 94W16. Is location in a high density area? (Rule 603b)? Yes No17. Distance to the nearest building, public road, above ground utility or railroad: 6494 ft18. Distance to nearest property line: 476 ft 19. Distance to nearest well permitted/completed in the same formation: 276 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	139-73	40	SESE
Williams Fork	WMFK	139-73	40	SESE

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached

25. Distance to Nearest Mineral Lease Line: 613 ft 26. Total Acres in Lease: 269

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: Closed Loop

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20	16	Line Pipe	100	16	100	0
SURF	12+1/4	8+5/8	32	1,500	545	1,500	0
1ST	7+7/8	4+1/2	11.6	10,288	450	10,288	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments The Production Casing Top of Cement will be 200 feet above Top of Gas. The surface Casing Setting Depth and Cement Bottom was changed to 1,500 feet as approved by the BLM. All conditions are the same as prior approved permit. This well is part of the RULISON 17M Pad. The pad has been built. This re-file will not require any expansion/additional surface disturbance of the pad. The pad is located in Project Rulison 3-Mile Radius Tier II. DOE was notified 1/30/09. A closed loop pitless system will be used for this APD. This location does not require a variance from any of the rules listed in COGCC Rule 306.d (1). (A).(ii). This pad is not in a wildlife restricted surface occupancy area. This location is in a Sensitive Wildlife Habitat, however, a Wildlife Mitigation Plan was executed with the CDOW on May 24th, 2010, that specifically covers this pad and it is valid for six years.

34. Location ID: 414152

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Tania McNutt

Title: Regulatory Analyst Date: _____ Email: tmcnutt@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER
05 045 18777 00

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name	Doc Description
400084516	30 DAY NOTICE LETTER	30 Day Notice.pdf
400084517	SURFACE AGRMT/SURETY	SUA.pdf
400084519	PLAT	RUL 17M Double B Ranch 18-44B_plat.pdf

Total Attach: 3 Files