



Andrews, David

From: Bascom, Brent [Brent.Bascom@Williams.com]
Sent: Tuesday, September 21, 2010 11:32 AM
To: Andrews, David
Subject: RE: Post Surface casing & cementing TR 344-27-597

David,
Sorry about the missing information.

Lead slurry, 442 bbl, 1123 sx, 12.3 ppg, 2.21 ft³/sk
Tail Slurry, 94 bbl, 257 sx, 12.6 ppg, 2.01 ft³/sk
Top Out Slurry, 77 bbl, 262 sx, 14.2 ppg, 1.65 ft³/sk

Thanks,

Brent Bascom

From: Andrews, David [David.Andrews@state.co.us]
Sent: Monday, September 20, 2010 6:26 PM
To: Bascom, Brent
Cc: Longworth, Mike
Subject: RE: Post Surface casing & cementing TR 344-27-597

Brent,

Please reply with the following Information:

- Cement Yield (cf/sk) for the lead, tail, and topout cement
- Slurry weight (ppg) for the tail cement.

Thanks,

David D. Andrews, P.E., P.G.

Engineering Supervisor - Western Colorado

State of Colorado

Oil and Gas Conservation Commission

707 Wapiti Court, Suite 204

Rifle, Colorado 81650

Office Phone: (970) 625-2497 Ext. 1

Cell Phone: (970) 456-5262

Fax: (970) 625-5682

E-mail: David.Andrews@state.co.us

Website: <http://www.colorado.gov/cogcc>

From: Bascom, Brent [mailto:Brent.Bascom@Williams.com]

Sent: Monday, September 20, 2010 6:42 AM

To: Bascom, Brent; Jackson, Jim; Beougher, Justin; Scharf, Allan; Cass, Lynn; Andrews, David; Bascom, Kenneth; Ragsdale, Ted; Longworth, Mike; Hancock, Scott

Subject: RE: Post Surface casing & cementing TR 344-27-597

Williams Production RMT Co. Drilled 14 3/4" Surface hole to a total depth of 2940' ,@ 20:00 PM, 09/18/2010, on the TR 344-27-597, API# 05-045-19222-00, Sec.27-T5S-R97W, Garfield County Co. and set 9 5/8", 32.3# H-40 surface casing @ 2930' on Sunday 09/19/2010.

Cement details.

single stage cement.

442 BBL (1123 SX) 12.3# Poz-A Lead Cement + 94 bbl (257 sx) Poz/A Tail cement. Displace w/ 225 bbl fresh water. Lift pressure 627 psi @ 1 bbl/min, Land plug w/ 904 psi . Floats held. No returns. Top fill to surface w/ 77 bbl(262 sx) 14.2 RFC cement. Hole stayed full.

Please call or email with any questions.

Thanks,

Brent Bascom

Williams Production

Cyclone 32

281-840-6548