



02054551

PETROLEUM DEVELOPMENT CORPORATION

State Contact: David Andrews david.andrews@state.co.us

WELL NAME PUCKETT 11C-24D

DATE 09/21/2010

API# 05-045-16105-00

LEASE#

PERMIT #

CASING AND HOLE INFORMATION

DEPTH HOLE 2677
CASING 9 5/8 36#, 8rD, ST&C
DEPTH SET 2651.81

Cement report

Company : BJ


CASING STRING:

LEAD: PREMLITEHS plus additives 1494 sacks 12.5 ppg 1.95 yld 519.72 bbl slurry mixed @ 5 bbl/min

TAIL: TYPE III plus additives 170 sacks 14.2 ppg 1.47 yld 45 bbl slurry mixed @ 3.5 bbl/min

DISPLACED Displaced w/ 199 bbls water @ 8 Dwn To 4 bbl/min bumped plug w/ 11135 psi Float held, NO RETURNS
PRESSURE BEFORE BUMPING PLUG: 330, plug bumped at 1135 PSI
RETURN: 0 returns

COMENTS:
TOP OUTS 1:00 WAITED 4 HOURS TO TOP OUT
300 SKS OF TYPE III W/ADDITIVES, Returns to surface, cement fell back 3 feet and stayed



Any Questions or problems please advise

Miles Pierson
801 - 520 - 3534