

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400094723

Plugging Bond Surety

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

 OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒
Refiling ☐Sidetrack ☐

3. Name of Operator: ENCANA OIL &amp; GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: MIRACLE PFISTER Phone: (720)876-3761 Fax: (720)876-4861

Email: miracle.pfister@encana.com

7. Well Name: KEINATH FEDERAL Well Number: 9-12H2 (C100U)

8. Unit Name (if appl): ORCHARD Unit Number: COC 66496X

9. Proposed Total Measured Depth: 14110

## WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 10 Twp: 8S Rng: 96W Meridian: 6

Latitude: 39.368668 Longitude: -108.099242

 Footage at Surface: 1023 FNL/FSL 1544 FEL/FWL  
 FNL FWL

11. Field Name: GRAND VALLEY Field Number: 31290

12. Ground Elevation: 5568 13. County: MESA

## 14. GPS Data:

Date of Measurement: 03/30/2010 PDOP Reading: 2.0 Instrument Operator's Name: C.D. SLAUGH

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.
 Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
 706 FNL 673 FWL 2434 FSL 570 FWL  
 Sec: 10 Twp: 8S Rng: 96W Sec: 9 Twp: 8S Rng: 96W
16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 3200 ft

18. Distance to nearest property line: 236 ft 19. Distance to nearest well permitted/completed in the same formation: 240 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES			
MANCOS	MNCAB			
NIOBRARA	NB-FR			
WILLIAMS FORK	WMFK			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC58674

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

8S-96W SEC 9: NE, S2NW, S2 SEC 10: W2NW, SW, W2SE SEC 14: SWNW, NWSW, SESW SEC 15: W2E2, SENE, S2, NESE, SEC 16: ALL

25. Distance to Nearest Mineral Lease Line: 570 ft 26. Total Acres in Lease: 2200

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	20	LINEPIPE	40	5	40	0
SURF	14+3/4	10+3/4	40.5	1,400	665	1,400	0
1ST	9+7/8	7+5/8	29.7	7,483	1,019	7,483	0
2ND	6+1/2	5	23.2	14,110	440	14,110	0

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments THE NEAREST DISTANCE IS TO A BUILDING AND ABOVE GROUND UTILITY. TOP OF INTERMEDIATE CASING WILL BE 200 FT ABOVE THE MSVD. TOP OF THE PRODUCTION CASING WILL BE 500 FT INSIDE THE INTERMEDIATE CASING.

34. Location ID: 334093

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: MIRACLE PFISTER

Title: REGULATORY ANALYST Date: \_\_\_\_\_ Email: miracle.pfister@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

API NUMBER

05

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**Attachment Check List**

Att Doc Num	Name	Doc Description
400094733	FED. DRILLING PERMIT	Keinath Federal 19-12H2 BLM APD.pdf
400094734	30 DAY NOTICE LETTER	30 Day Drilling Notice - Mary Satterfield C10OU 9-14-10.pdf
400094736	SURFACE AGRMT/SURETY	C10OU SDA.pdf
400094737	PLAT	Keinath Federal 9-12H2 (C10OU) Plat.pdf
400094738	DEVIATED DRILLING PLAN	Pages from Encana (C10OU Pad) Keinath Federal 9-12H2 Plan #1.pdf

Total Attach: 5 Files