

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐
Sidetrack ☐

Document Number:

400075091

Plugging Bond Surety

20040071

3. Name of Operator: ANTERO RESOURCES PICEANCE CORPORATION

4. COGCC Operator Number: 10079

5. Address: 1625 17TH ST STE 300

City: DENVER State: CO Zip: 80202

6. Contact Name: Hannah Knopping Phone: (303)357-6412 Fax: (303)357-7315

Email: hknopping@anteroresources.com

7. Well Name: Frei Well Number: A3

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7006

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 7 Twp: 6S Rng: 91W Meridian: 6

Latitude: 39.535878 Longitude: -107.603260

Footage at Surface: 504 FNL/FSL FSL 920 FEL/FWL FWL

11. Field Name: Kokopelli Field Number: 47525

12. Ground Elevation: 5607 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 05/10/2010 PDOP Reading: 2.4 Instrument Operator's Name: Scott Aibner

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FSL Bottom Hole: FNL/FSL FNL/FSL
728 FNL 1731 FWL 728 FNL 1731 FWL
Sec: 18 Twp: 6S Rng: 91W Sec: 18 Twp: 6S Rng: 91W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 573 ft

18. Distance to nearest property line: 308 ft 19. Distance to nearest well permitted/completed in the same formation: 304 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	513, 523-6	160	Part of W2
Williams Fork	WMFK	513, 523-6	160	Part of W2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached lease map.

25. Distance to Nearest Mineral Lease Line: 423 ft 26. Total Acres in Lease: 40

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: Onsite if meet table 910

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	16	55#	60	177	60	0
SURF	12+1/4	8+5/8	24/32#	1,000	416	1,000	0
1ST	7+7/8	4+1/2	11.6#	7,006	717	7,006	900

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments First String/Production TOC will be >500 feet above Top of Gas.
#24-The well distance given is to a lease line which in this case is also the unit boundary line. BHL complies with spacing order with respect to distance to unit boundary.
Spacing unit configuration for Section 18-T6S-R91W: Part of W/2, described as NENW, Lots 1-3 (~160.9 acre unit)

34. Location ID: 417777

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Hannah Knopping

Title: Permit Representative Date: 7/13/2010 Email: hknopping@anteroresources.co

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 9/29/2010

API NUMBER

05 045 19959 00

Permit Number: _____ Expiration Date: 9/28/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.
- 2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE
- 3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE
- 4) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 380 FEET DEEP.
- 5) THE BRADENHEAD PRESSURE MONITORING, REQUIRED BY THE MAMM CREEK FIELD NOTICE TO OPERATORS, MUST BE REPORTED TO COGCC ON THE NEXT FOUR WELLS DRILLED ON THIS PAD (WELLS 5 - 8) VIA SUNDRY NOTICE. APPROVAL IS REQUIRED PRIOR TO STARTING TO DRILL THE 9TH PRODUCTION HOLE INTERVAL ON THE PAD. EMAIL SUNDRY NOTICE TO KEVIN.KING@STATE.CO.US

Attachment Check List

Att Doc Num	Name	Doc Description
400075091	FORM 2 SUBMITTED	LF@2507333 400075091
400075537	WELL LOCATION PLAT	LF@2507335 400075537
400075538	LEASE MAP	LF@2507336 400075538
400075539	30 DAY NOTICE LETTER	LF@2507337 400075539
400075540	ACCESS ROAD MAP	LF@2507338 400075540
400075541	SURFACE AGRMT/SURETY	LF@2507339 400075541
400075906	DEVIATED DRILLING PLAN	LF@2507340 400075906

Total Attach: 7 Files

General Comments

User Group	Comment	Comment Date
Permit	PERMITTING PASSED.	8/12/2010 8:59:45 AM
Engineer	Permit On Hold by engineering. KK	8/12/2010 8:59:32 AM

Total: 2 comment(s)

Error: Subreport could not be shown.