

# Map Unit Description

Rifle Area, Colorado, Parts of Garfield and Mesa Counties

## 53 Parachute-Rhone loams, 5 to 30 percent slopes

### Setting

Elevation: 7600 to 8600 feet

### Composition

Parachute and similar soils: 55 percent

Rhone and similar soils: 30 percent

### Description of Parachute

#### Setting

Landform: Mountainsides, ridges

Down-slope shape: Convex

Across-slope shape: Convex

Parent material: Marl and/or residuum weathered from sandstone

#### Properties and Qualities

Slope: 5 to 30 percent

Depth to restrictive feature: 20 to 40 inches to Paralithic bedrock

Drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low or moderately high (0.06 to 0.20 in/hr)

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate maximum: 0 percent

Gypsum maximum: 0 percent

Available water capacity: Low (about 3.3 inches)

#### Interpretive Groups

Land capability (non irrigated): 6e

Ecological site: Mountain Loam (R048AY228CO)

#### Typical Profile

0 to 5 inches: loam

5 to 18 inches: loam

18 to 29 inches: extremely channery loam

29 to 33 inches: unweathered bedrock

### Description of Rhone

#### Setting

Landform: Mountainsides, ridges

Down-slope shape: Convex

Across-slope shape: Convex

Parent material: Marl and/or residuum weathered from sandstone

#### Properties and Qualities

Slope: 5 to 20 percent

Depth to restrictive feature: 40 to 60 inches to Paralithic bedrock

Drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low or moderately high (0.06 to 0.20 in/hr)

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate maximum: 0 percent

Gypsum maximum: 0 percent

Available water capacity: Moderate (about 6.2 inches)

#### Interpretive Groups

Land capability (non irrigated): 6e

Ecological site: Mountain Loam (R048AY228CO)

#### Typical Profile

0 to 8 inches: loam

8 to 28 inches: sandy clay loam

28 to 52 inches: very channery sandy clay loam

52 to 56 inches: unweathered bedrock

## Map Unit Description

Rifle Area, Colorado, Parts of Garfield and Mesa Counties