

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

Document Number:
400081809
Plugging Bond Surety

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY 4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000
City: DENVER State: CO Zip: 80202

6. Contact Name: Greg Davis Phone: (303)606-4071 Fax: (303)629-8272
Email: Greg.J.Davis@Williams.com

7. Well Name: Jolley Well Number: KP 443-18

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7405

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 17 Twp: 6S Rng: 91W Meridian: 6
Latitude: 39.525982 Longitude: -107.587048

Footage at Surface: 2041 FNL/FSL FSL 225 FEL/FWL FWL

11. Field Name: Kokopelli Field Number: 47525

12. Ground Elevation: 6206 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 01/21/2010 PDOP Reading: 2.4 Instrument Operator's Name: C. Strouse

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____
1815 FSL 651 FEL 1815 FSL 651 FEL
Sec: 18 Twp: 6S Rng: 91W Sec: 18 Twp: 6S Rng: 91W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 232 ft

18. Distance to nearest property line: 184 ft 19. Distance to nearest well permitted/completed in the same formation: 1347 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork lles	WFILS	513-4		

21. Mineral Ownership: Fee State Federal Indian Lease #: COC51146

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached

25. Distance to Nearest Mineral Lease Line: 1815 ft 26. Total Acres in Lease: 1200

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: Re-use and evaporation

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	18	48#	45	25	45	0
SURF	13+1/2	9+5/8	32.3#	741	259	741	0
1ST	7+7/8	4+1/2	11.6	7,405	651	7,405	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments COC51146 See Williams Master APD dated 11/1/09. Well shall be cemented 500' above the top of gas.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Greg Davis

Title: Supervisor Permits Date: 8/5/2010 Email: Greg.J.Davis@Williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 10/4/2010

Permit Number: _____ Expiration Date: 10/3/2012

API NUMBER
05 045 20005 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.
- 2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE
- 3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE
- 4) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 240 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
1791802	LEGAL/LEASE DESCRIPTION	LF@2552429 1791802
400081809	FORM 2 SUBMITTED	LF@2520508 400081809
400081905	WELL LOCATION PLAT	LF@2520509 400081905
400081906	TOPO MAP	LF@2520510 400081906
400081986	SURFACE AGRMT/SURETY	LF@2520511 400081986
400082478	DEVIATED DRILLING PLAN	LF@2520512 400082478
400082628	FED. DRILLING PERMIT	LF@2520513 400082628

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Received reference map and photos. Williams considering changing from 4 wells to 14 wells on this pad.	10/1/2010 11:46:50 AM
Permit	Received lease via email 9/28/10 BY	9/29/2010 5:24:20 AM
Permit	Requested general location of reference area, as not indicated on reference area map or given as description in comments. Called Greg Davis 9/28/10 Form 2 ready to pass with explanation of above. Requested lease map or discription. BY WO COA'S	9/28/2010 12:16:08 PM

Total: 3 comment(s)

Error: Subreport could not be shown.