

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400086121

Plugging Bond Surety

20060137

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☒

Sidetrack ☐

3. Name of Operator: OXY USA WTP LP

4. COGCC Operator Number: 66571

5. Address: P O BOX 27757

City: HOUSTON State: TX Zip: 77227

6. Contact Name: Joan Proulx Phone: (970)263.3641 Fax: (970)263.3694  
Email: joan\_proulx@oxy.com

7. Well Name: Cascade Creek Well Number: 697-05-80B

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 9736

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 8 Twp: 6S Rng: 97W Meridian: 6

Latitude: 39.542097 Longitude: -108.238028

Footage at Surface: 948 FNL/FSL FNL 1090 FEL/FWL FEL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 8419 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 08/03/2010 PDOP Reading: 3.7 Instrument Operator's Name: Ron Rennke

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 253 FSL 423 FEL 423 FEL 423 FEL 423  
Bottom Hole: FNL/FSL 253 FSL 423 FEL 423 FEL 423  
Sec: 5 Twp: 6S Rng: 97W Sec: 5 Twp: 6S Rng: 97W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 5307 ft

18. Distance to nearest property line: 2890 ft 19. Distance to nearest well permitted/completed in the same formation: 330 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	510-48		
Williams Fork	WMFK	510-15		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See attached Mineral Lease Description

25. Distance to Nearest Mineral Lease Line: 4854 ft 26. Total Acres in Lease: 9520

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20+0/0	16+0/0	65	100	4	100	0
SURF	14+3/4	9+5/8	36	2,690	1,420	2,690	0
1ST	8+3/4	4+1/2	11.6	9,726	2,109	9,726	5,586

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Oxy is both the surface and mineral owner; Rule 305 and 306 are waived. The well pad has been constructed and there is one producing well on this location. A semi-closed loop system will be used. Oxy will provide appropriate housing for essential personnel in order to conduct safe, efficient drilling operations at this well site. The plat references a "blooie pit;" this is not a pit but a flare box. Per GarCo Vacation Ordinance dated 10-5-1987, CR 213 is now OXY's private property north of Sec 8, 7S, 97W, 6 PM.

34. Location ID: 324100

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Joan Proulx

Title: Regulatory Analyst Date: 8/20/2010 Email: joan\_proulx@oxy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 10/5/2010

Permit Number: \_\_\_\_\_ Expiration Date: 10/4/2012

**API NUMBER**

05 045 18733 00

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

3) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 430 FEET DEEP.

**Attachment Check List**

Att Doc Num	Name	Doc Description
400086121	FORM 2 SUBMITTED	LF@2527769 400086121
400086125	MINERAL LEASE MAP	LF@2527770 400086125
400086127	TOPO MAP	LF@2527771 400086127
400086130	DEVIATED DRILLING PLAN	LF@2527772 400086130
400086131	WELL LOCATION PLAT	LF@2527773 400086131

Total Attach: 5 Files

Error: Subreport could not be shown.