

Berry Petroleum Company
OM10B K15 696
API # 05-045-14974-0000
NESW Sec 15 Twn 6S Rng 96W
Garfield County, Colorado

Prepared Charles Durkoop
Updated 6/10/2010

Rig Patterson 175

8498 KB
8476 GL
22 KB-GL

BHT

20" Conductor @ 142'

Csg Cut @ 639' 4-1/2" Csg patch PTST 6000#

16" hole @ 3260' 74 jts of 9-5/8" 36# J-55 @ 3225' Para inj @ 2866'
Cmt w/1305 sx @ 11.6 ppg & 3.20 yield lead & 100 sx type III 14.2 ppg & 1.52 yield

Equipment in Hole	Qty	Length	Depth
KB		22.00	22.00
Tubing Hanger		0.80	22.80
2-3/8" EU 8RD N80 tbg	263	8559.60	8582.40
2-3/8" F nipple		0.81	8583.21
2 3/8" EU 8rd tbg	1	32.56	8615.77
Notched collar		0.40	8616.17

TOC @ 4410'

TOCC @ 6134'

7/1/2008 Spud well
7/4/2008 Set Surf
7/13/2008 Set Prod
8/19/2008 Cut csg & run patch
10/10/2008 Frac 3 stgs
1/13/2010 D/O CFP
1/15/2010 PTST to 7000 @ 8841'
1/28/2010 Set CIBP (3)
1/31/2010 Frac Stgs 4-7
2/4/2010 D/O CFP
2/11/2010 Land tbg
2/16/2010 Move tbg

Tag @ 8780'

CIBP @ 8790'
CIBP @ 8866'
CIBP @ 8870'

Stage 7: 7967 - 8109 @ 2 SPF (30 shots). Frac'd w/ 101,286 lbs 30/50 white sand; 5,363 bls slickwater; led w/ 500gal 7.5% acid

Stage 6: 8143 - 8322 @ 2 SPF (30 shots). Frac'd w/ 164,094 lbs 30/50 white sand; 8,493 bls slickwater; led w/ 500gal 7.5% acid

Stage 5: 8368 - 8590 @ 2 SPF (30 shots). Frac'd w/ 150,823 lbs 30/50 white sand; 7,830 bls slickwater; led w/ 500gal 7.5% acid

Stage 4: 8641 - 8789 @ 2 SPF (26 shots). Frac'd w/ 158,400 lbs 30/50 white sand; 8,243 bls slickwater; led w/ 500gal 7.5% acid

Stage 3: 8905 - 9099 @ 2 SPF (24 shots). Frac'd w/ 124,171 lbs 30/50 white sand; 3,363 bls slickwater; led w/ 750gal 15% acid

Stage 2: 9392 - 9600 @ 2 SPF (20 shots). Frac'd w/ 80,149 lbs 30/50 white sand; 2,239 bls slickwater; led w/ 750gal 15% acid

Stage 1: 9794 - 9979 @ 2 SPF (24 shots). Frac'd w/ 106,046 lbs 30/50 white sand; 2,921 bls slickwater; led w/ 750gal 15% acid

Marker jts @ 5044 - 65' &
7804 - 65'

8-3/4" hole @ 7350' & 7-7/8" hole @ 10346'
249 jts 4-1/2" 11.6# P110 & I-100 prod csg @ 10316'
Cmt 660 @ 12.5 ppg, 2.69 yield

PBTD @ 10260' WL Tag 7/28/08
C/O @ 10009' on 1/13/10
TD @ 10346'