

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

Document Number:
400086319
Plugging Bond Surety
20060137

3. Name of Operator: OXY USA WTP LP 4. COGCC Operator Number: 66571

5. Address: P O BOX 27757
City: HOUSTON State: TX Zip: 77227

6. Contact Name: Joan Proulx Phone: (970)263.3641 Fax: (970)263.3694
Email: joan_proulx@oxy.com

7. Well Name: Cascade Creek Well Number: 697-09-19A

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 10138

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 8 Twp: 6S Rng: 97W Meridian: 6
Latitude: 39.541960 Longitude: -108.238146

Footage at Surface: 998 FNL/FSL FNL 1124 FEL/FWL FEL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 8424 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 08/03/2010 PDOP Reading: 2.3 Instrument Operator's Name: Ron Rennke

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1444 FNL 1447 FWL 1480 FNL 1656 FWL
Bottom Hole: FNL/FSL 1480 FNL 1656 FWL
Sec: 9 Twp: 6S Rng: 97W Sec: 9 Twp: 6S Rng: 97W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 5307 ft

18. Distance to nearest property line: 2890 ft 19. Distance to nearest well permitted/completed in the same formation: 393 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	510-48		
Williams Fork	WMFK	510-15		

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached Mineral Lease Description

25. Distance to Nearest Mineral Lease Line: 6920 ft 26. Total Acres in Lease: 9520

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20+0/0	16+0/0	65	100	4	100	0
SURF	14+3/4	9+5/8	36	2,690	1,420	2,690	0
1ST	8+3/4	4+1/2	11.6	10,129	2,216	10,129	5,936

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Oxy is both the surface and mineral owner; Rule 305 and 306 are waived. The well pad has been constructed and there is one producing well on this location. A semi-closed loop system will be used. Oxy will provide appropriate housing for essential personnel in order to conduct safe, efficient drilling operations at this well site. The plat references a "blooie pit;" this is not a pit but a flare box. Per GarCo Vacation Ordinance dated 10-5-1987, CR 213 is now OXY's private property north of Sec 8, 7S, 97W, 6 PM.

34. Location ID: 324100

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Joan Proulx

Title: Regulatory Analyst Date: 8/20/2010 Email: joan_proulx@oxy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 10/8/2010

Permit Number: _____ Expiration Date: 10/7/2012

API NUMBER

05 045 20020 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

3) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 430 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
2089348	LEGAL/LEASE DESCRIPTION	LF@2599291 2089348
400086319	FORM 2 SUBMITTED	LF@2527844 400086319
400086323	MINERAL LEASE MAP	LF@2527845 400086323
400086324	TOPO MAP	LF@2527846 400086324
400086325	WELL LOCATION PLAT	LF@2527847 400086325
400086326	DEVIATED DRILLING PLAN	LF@2527848 400086326

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Distance to mineral lease line changed to 6,920'	10/8/2010 11:38:55 AM

Total: 1 comment(s)

Error: Subreport could not be shown.