

FORM
5A

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

2555547

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120 4. Contact Name: CINDY VUE
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6832
3. Address: P O BOX 173779 Fax: (720) 929-7832
City: DENVER State: CO Zip: 80217-37

5. API Number 05-123-27032-00 6. County: WELD
7. Well Name: WIEDEMAN Well Number: 25-20
8. Location: QtrQtr: NWSE Section: 20 Township: 5N Range: 66W Meridian: 6
9. Field Name: _____ Field Code: _____

Completed Interval

FORMATION: <u>NIOBRARA-CODELL</u>	Status: <u>PRODUCING</u>
Treatment Date: <u>03/16/2010</u>	Date of First Production this formation: <u>05/18/2010</u>
Perforations Top: <u>7144</u> Bottom: <u>7484</u>	No. Holes: <u>116</u> Hole size: <u>38/100</u>
Provide a brief summary of the formation treatment:	Open Hole: <input type="checkbox"/>
<u>NB PERF 7144-7368 HOLES 62 SIZE 0.42 CD PERF 7466-7484 HOLES 54 SIZE 0.38 FRAC NB W/500 GAL 15% HCL & 245,914 GAL SW W/200,460# 40/70 & 4,000# 20/40 SB EXCEL. FRAC CD W/203,910 GAL SW W/150,260# 40/70 & 4,000# 20/40 SB EXCEL.</u>	
This formation is commingled with another formation: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Test Information:	
Date: <u>05/30/2010</u> Hours: _____ Bbls oil: _____ Mcf Gas: _____ Bbls H2O: _____	
Calculated 24 hour rate: _____ Bbls oil: <u>47</u> Mcf Gas: <u>282</u> Bbls H2O: <u>0</u> GOR: <u>6000</u>	
Test Method: <u>FLOWING</u> Casing PSI: <u>1725</u> Tubing PSI: _____ Choke Size: <u>12/64</u>	
Gas Disposition: <u>SOLD</u> Gas Type: <u>WET</u> BTU Gas: <u>1260</u> API Gravity Oil: <u>55</u>	
Tubing Size: _____ Tubing Setting Depth: _____ Tbg setting date: _____ Packer Depth: _____	
Reason for Non-Production: _____	
Date formation Abandoned: _____ Squeeze: <input type="checkbox"/> Yes <input type="checkbox"/> No If yes, number of sacks cmt _____	
Bridge Plug Depth: _____ Sacks cement on top: _____	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CINDY VUE

Title: REGULATORY ANALYST II Date: 6/9/2010 Email CINDY.VUE@ANADARKO.COM

Based on the information provided herein, this Completed Interval Report (Form 5A) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____

David S. Neslin

Director of COGCC

Date: 10/12/2010

Attachment Check List

Att Doc Num	Name	Doc Description
2555547	FORM 5A SUBMITTED	LF@2506080 2555547

Total Attach: 1 Files