



123-30102



# ANADARKO PETROLEUM

Location: COLORADO Slot: SLOT#13 VARRA 14-2 (1225'FSL & 1553'FWL)  
Field: WELD COUNTY (ANADARKO) Well: VARRA-14-2  
Facility: SEC.02-T2N-R68W Wellbore: VARRA 14-2 PWB



Plot reference wellbore VARRA 14-2 (R68W) PWB  
True vertical depths are referenced to XTREME 5 (RT)  
Sectional depths are referenced to XTREME 5 (RT)  
XTREME 5 (RT) is 1500 ft from the surface  
Mean Sea Level is 1500 ft from the surface  
Coordinates are in feet referenced to 500

Grid System: NAD83 / Lambert Conformal State Plane, Northern Zone (500) US feet  
North Reference: True north  
Scale: True distance  
Depth: in feet  
Created by: Isotrac on 1/28/2010

Well Profile Data							
Design Comment	MD (ft)	Incl (°)	Az (°)	TVD (ft)	Local N (ft)	Local E (ft)	DLS (°100ft)
Tie On	17.00	0.00	143.108	17.00	0.00	0.00	0.00
End of Tangent	910.00	0.00	143.108	910.00	0.00	0.00	0.00
Build (S)	1510.00	12.00	143.108	1505.62	50.07	37.58	2.00
End of Tangent (S)	5187.67	12.00	143.108	5102.93	661.59	496.60	0.00
Drop (S)	5787.67	0.00	143.108	5696.55	711.66	534.18	2.00
End of Tangent	8013.12	0.00	143.108	7924.00	711.66	534.18	0.00

