

BOPCO L.P.

YELLOW CREEK FEDERAL 4-11-1

Lat: 40.00393 – Long. 108.40347

Lot 8, SECTION 4, T1S, R98W

Rio Blanco County, Colorado

Federal Lease: COC-59393

Stormwater Management

Stormwater Management will be managed under BOPCO, L.P. Stormwater Management Plan (SWMP), Yellow Creek Field, Rio Blanco County, Colorado, updated March 2007. The SWMP is covered under the CDPS large construction permit COR-030000.

Prior to construction a stormwater “perimeter” will be built around the site for initial work purposes. Once the pad construction is completed, BOPCO, L.P. Stormwater Administrator will inspect the site and install any necessary Erosion Control Devices to manage sediment discharge from the pad. These devices may include but are not limited to:

Rock Checks Dams

V- Ditches

Rock Armoring of Access Roads

Erosion Control Blankets

Straw Waddles

Silt Fencing

Berm/Diversion

Outlet Protection

Once the final stormwater erosion control devices are installed they will be mapped in GIS and a diagram of the site will be drafted and included as part of the SWMP as required by the CDPHE General Permit.

This site will be inspected every 14 days and 72 hours after any major storm event. These inspections will be recorded and documented in the SWMP onsite at the Yellow Creek Field gas plant. Any necessary repairs or modification will be made and documented in the SWMP. An updated site diagram will be included in the SWMP.

Spill Prevention Control and Counter Measures (SPCC)

Once the well is drilled and completed BOPCO, L.P. SPCC plan will be amended to include the site as part of the plan.