

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE

ET

OE

ES

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐Refiling ☐Sidetrack ☐

Document Number:

400083710

Plugging Bond Surety

20030009

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: Susan Miller Phone: (303)228-4246 Fax: (303)228-4286

Email: smiller@nobleenergyinc.com

7. Well Name: WEIDENKELLER PC

Well Number: G01-27D

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 7581

## WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 1 Twp: 4N Rng: 65W Meridian: 6

Latitude: 40.345960 Longitude: -104.613530

Footage at Surface: 901 FNL 2047 FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4755 13. County: WELD

## 14. GPS Data:

Date of Measurement: 06/04/2010 PDOP Reading: 2.9 Instrument Operator's Name: Michael Chad Dilka

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
75 FNL 1480 FEL 75 FNL 1480 FEL  
Sec: 1 Twp: 4N Rng: 65W Sec: 1 Twp: 4N Rng: 65W16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 730 ft

18. Distance to nearest property line: 197 ft 19. Distance to nearest well permitted/completed in the same formation: 811 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CODL	407-87	160	See Comments
Niobrara	NBRR	407-87	160	See Comments

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
T4N-R65W Section 1: N/2NE/4.

25. Distance to Nearest Mineral Lease Line: 1480 ft 26. Total Acres in Lease: 80

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	650	230	650	0
1ST	7+7/8	4+1/2	11.6	7,581	707	7,581	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used. First string top of cement will be 200' above the Niobrara formation. This is part of a 7-well, multi-well pad permit which includes: Weidenkeller PC G01-30D, G01-29D, G01-28D, G01-27D, G01-31D, G01-20D and G01-21D. 2A filed under Weidenkeller PC G01-30D, document no. 400083579. Unit Configuration: T4N-R65W Sec. 1: N/2NE/4; T5N-R65W Sec. 36: S/2SE/4.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Susan Miller

Title: Regulatory Analyst II Date: \_\_\_\_\_ Email: smiller@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

API NUMBER

05

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**Attachment Check List**

Att Doc Num	Name	Doc Description
400083729	30 DAY NOTICE LETTER	30 day notice.pdf
400091510	PROPOSED SPACING UNIT	318Ae Spacing Unit Map.pdf
400091511	PROPOSED SPACING UNIT	318Ae Spacing Unit Plat.pdf
400091512	WELL LOCATION PLAT	Approved Plat.pdf
400091513	DEVIATED DRILLING PLAN	Dir Drilling Plan.pdf
400099897	OTHER	20 Day Cert Letter.pdf
400099914	SURFACE AGRMT/SURETY	SUA.pdf
400100018	EXCEPTION LOC REQUEST	318Aa, Ae, Ac Request.pdf
400100019	EXCEPTION LOC WAIVERS	318Aa, Ae, Ac Waiver.pdf

Total Attach: 9 Files