

Weld County, Colorado, Northern Part

45—Olney fine sandy loam, 6 to 9 percent slopes

Map Unit Setting

Elevation: 3,500 to 5,800 feet
Mean annual precipitation: 11 to 15 inches
Mean annual air temperature: 46 to 54 degrees F
Frost-free period: 125 to 175 days

Map Unit Composition

Olney and similar soils: 85 percent
Minor components: 15 percent

Description of Olney

Setting

Landform: Plains
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Calcareous loamy alluvium

Properties and qualities

Slope: 6 to 9 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.57 to 2.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum content: 15 percent
Maximum salinity: Nonsaline (0.0 to 2.0 mmhos/cm)
Available water capacity: Moderate (about 8.1 inches)

Interpretive groups

Land capability (nonirrigated): 6e
Ecological site: Loamy Plains (R067BY002CO)

Typical profile

0 to 6 inches: Fine sandy loam
6 to 18 inches: Sandy clay loam
18 to 60 inches: Sandy loam
60 to 64 inches: Sandy loam

Minor Components

Stoneham

Percent of map unit: 5 percent

Vona

Percent of map unit: 5 percent

Ascalon

Percent of map unit: 5 percent

Data Source Information

Soil Survey Area: Weld County, Colorado, Northern Part

Survey Area Data: Version 8, Apr 30, 2009