

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

2590163

Plugging Bond Surety

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐

Sidetrack ☐

3. Name of Operator: WEXPRO COMPANY

4. COGCC Operator Number: 95960

5. Address: P O BOX 45003

City: SALT LAKE CITY State: UT Zip: 84145-0601

6. Contact Name: DEE FINDLAY Phone: (307)922-5608 Fax: (307)352-7575
Email: DEE.FINDLAY@QUESTAR.COM

7. Well Name: POWDER WASH GOVERNMENT Well Number: 15

8. Unit Name (if appl): POWDER WASH Unit Number: COC047671
A

9. Proposed Total Measured Depth: 9857

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 5 Twp: 11N Rng: 97W Meridian: 6
Latitude: 40.935453 Longitude: -108.319914

Footage at Surface: 161 FNL/FSL FSL 1444 FEL/FWL FWL

11. Field Name: POWDER WASH Field Number: 69800

12. Ground Elevation: 7037 13. County: MOFFAT

14. GPS Data:

Date of Measurement: 07/21/2008 PDOP Reading: 3.7 Instrument Operator's Name: DAVID KAY

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 112 FNL 2338 FEL FEL Bottom Hole: FNL/FSL 112 FNL 2338 FEL FEL
Sec: 8 Twp: 11N Rng: 97W Sec: 8 Twp: 11N Rng: 97W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2885 ft

18. Distance to nearest property line: 3 mi 19. Distance to nearest well permitted/completed in the same formation: 920 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
FORT UNION	FTUN			
WASATCH	WSTC			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COD004086
6

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED MAP.

25. Distance to Nearest Mineral Lease Line: 112 ft 26. Total Acres in Lease: 80

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: RESERVE PIT

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	20	STEELPIPE	80	8	80	0
SURF	12+1/4	9+5/8	36#	1,500	820	1,500	0
1ST	7+7/8	4+1/2	13.5#	9,857	1,432	9,857	0

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments THIS WELL IS COVERED BY THE POWDER WASH AND JACKS DRAW UNIT WELLS LOCATION SURFACE USE PLAN DATED 01/01/2010. THIS WELL WILL BE LOCATED ON THE FIVE WELL PAD OF: BW MUSSER NO. 34, BW MUSSER NO. 42 AND POWDER WASH GOVERNMENT NO. 15, NO. 16, NO. 17. THE FORM 2A HAS BEEN SUBMITTED FOR BW MUSSER #34

34. Location ID: 416367

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: G.T. NIMMO

Title: OPERATIONS MGR Date: 9/3/2010 Email: DEE.FINDLAY@QUESTAR.CO

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nash Director of COGCC Date: 10/19/2010

API NUMBER

05 081 07628 00

Permit Number: _____ Expiration Date: 10/18/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) CEMENT ON PRODUCTION CASING MUST BE AT LEAST 200' ABOVE TOP OF FT. UNION AND COMPLY WITH RULES 209 AND 317.I. SEGREGATE OIL, GAS, AND FRESH-WATER-BEARING ZONES AND PROTECT COAL SEAMS. VERIFY TOP WITH CBL.

(3) THE SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 72 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
2590163	APD ORIGINAL	LF@2540731 2590163
2590166	WELL LOCATION PLAT	LF@2540732 2590166
2590167	TOPO MAP	LF@2540733 2590167
2590168	MINERAL LEASE MAP	LF@2540756 2590168
2590169	ACCESS ROAD MAP	LF@2540755 2590169
2590170	DEVIATED DRILLING PLAN	LF@2540734 2590170
2590171	FED. DRILLING PERMIT	LF@2540735 2590171
2590172	DRILLING PLAN	LF@2540736 2590172

Total Attach: 8 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Changed distance to nearest well to 920', distance to lease line to 112' to match survey plat, and checked OGLA submittal box, zone type changed to multiple Added Related Forms inforamtion to tab	10/1/2010 12:43:33 PM
Permit	Is in SWH area (Form didn't come in at the same time as the 2A)	9/15/2010 9:56:08 AM

Total: 2 comment(s)

Error: Subreport could not be shown.