

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

 OIL ☐ GAS ☒ COALBED ☐ OTHER _____
 SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

 Refiling ☒
 Sidetrack ☐

Document Number:

400095066

Plugging Bond Surety

20040105

3. Name of Operator: BERRY PETROLEUM COMPANY4. COGCC Operator Number: 100915. Address: 1999 BROADWAY STE 3700City: DENVER State: CO Zip: 802026. Contact Name: Kallasandra Moran Phone: (303)999-4225 Fax: (303)999-4325Email: kmoran@bry-consultant.com7. Well Name: Long Ridge Well Number: 01A P15 595

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 12458

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 15 Twp: 5S Rng: 95W Meridian: 6Latitude: 39.610119 Longitude: -108.032341
 Footage at Surface: 1287 FNL/FSL FSL 305 FEL/FWL FEL
11. Field Name: Parachute Field Number: 6735012. Ground Elevation: 8391 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 07/12/2010 PDOP Reading: 2.0 Instrument Operator's Name: Ivan Martin/Construction Surveys15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL 209 FNL 405 FEL 209 FNL 405 FEL
 Bottom Hole: FNL/FSL 209 FNL 405 FEL
 Sec: 22 Twp: 5S Rng: 95W Sec: 22 Twp: 5S Rng: 95W
16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 22586 ft18. Distance to nearest property line: 286 ft 19. Distance to nearest well permitted/completed in the same formation: 306 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	510-13		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached mineral lease map

25. Distance to Nearest Mineral Lease Line: 405 ft 26. Total Acres in Lease: 25000

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☒ Yes ☐ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Total closed loop system

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	30	20	55	90	100	90	0
SURF	16	9+5/8	36	2,500	1,000	2,500	0
1ST	8+3/4	4+1/2	11.6	12,458	600	12,458	200

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments This well was originally permitted as the Long Ridge 16A P15 595 the new name as re-filed is Long Ridge 01A P15 595 (API# 05-045-13101). This well was originally permitted with a SHL location of 1201 FSL and 163 FEL the new SHL as re-filed is 1287 FSL and 305 FEL. This well was originally permitted with a BHL location of 985 FSL and 220 FEL the new BHL as re-filed is 209 FNL and 405 FEL. The location does NOT require a variance from any of the rules listed in Rule 306.d. (1). (A). (ii).
The location is NOT in a restricted surface occupancy area.
The location is NOT a sensitive wildlife habitat area.
The production casing Top of Cement will be 200' above the Top of Gas.
Berry Petroleum Company will be using a total closed loop system.

34. Location ID: 335864

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kallasandra M. Moran

Title: Permit Agent Date: _____ Email: kmoran@bry-consultant.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05 045 13101 00

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name	Doc Description
400095071	OTHER	Diesel Use and Cuttings Procedure.PDF
400095073	MINERAL LEASE MAP	Encana Mineral Lease Map.PDF
400095074	PLAT	Long Ridge 01A P15-595 Plat.pdf
400095076	TOPO MAP	LONG RIDGE P15-595 - Topo Map.pdf
400095181	30 DAY NOTICE LETTER	P15 30 Day Letter - Sent 9-22-2010.PDF
400101658	DEVIATED DRILLING PLAN	Berry Petroleum (SESE P15 595) LR01A Plan #1.pdf

Total Attach: 6 Files