

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400095119

Plugging Bond Surety

20040105

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

 OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐
Refiling ☒Sidetrack ☐3. Name of Operator: BERRY PETROLEUM COMPANY4. COGCC Operator Number: 100915. Address: 1999 BROADWAY STE 3700City: DENVER State: CO Zip: 802026. Contact Name: Kallasandra Moran Phone: (303)999-4225 Fax: (303)999-4325Email: kmoran@bry-consultant.com7. Well Name: Long Ridge Well Number: 01D P15 595

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 12433

## WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 15 Twp: 5S Rng: 95W Meridian: 6Latitude: 39.610199 Longitude: -108.032319
 Footage at Surface: 1317 FNL/FSL FSL 299 FEL/FWL FEL
11. Field Name: Parachute Field Number: 6735012. Ground Elevation: 8391 13. County: GARFIELD

## 14. GPS Data:

Date of Measurement: 07/12/2010 PDOP Reading: 2.0 Instrument Operator's Name: Ivan Martin/Construction Surveys15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL 193 FNL 241 FEL 193 FNL 241 FEL  
 Bottom Hole: FNL/FSL 193 FNL 241 FEL  
 Sec: 22 Twp: 5S Rng: 95W Sec: 22 Twp: 5S Rng: 95W
16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 22586 ft18. Distance to nearest property line: 286 ft 19. Distance to nearest well permitted/completed in the same formation: 406 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	510-13		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See attached mineral lease map.

25. Distance to Nearest Mineral Lease Line: 241 ft 26. Total Acres in Lease: 25000

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☒ Yes ☐ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Total closed loop system

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	30	20	55	90	100	90	0
SURF	16	9+5/8	36	2,500	1,000	2,500	0
1ST	8+3/4	4+1/2	11.6	12,433	600	12,433	200

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments This well was originally permitted as the Long Ridge 09B P15 595 the new name as re-filed is Long Ridge 01D P15 595 (API# 05-045-13104). This well was originally permitted with a SHL location of 1201 FSL and 163 FEL the new SHL as re-filed is 1287 FSL and 305 FEL. This well was originally permitted with a BHL location of 985 FSL and 220 FEL the new BHL as re-filed is 209 FNL and 405 FEL. The location does NOT require a variance from any of the rules listed in Rule 306.d. (1). (A). (ii).  
The location is NOT in a restricted surface occupancy area.  
The location is NOT a sensitive wildlife habitat area.  
The production casing Top of Cement will be 200' above the Top of Gas.  
Berry Petroleum Company will be using a total closed loop system.

34. Location ID: 335864

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Kallasandra M. Moran

Title: Permit Agent Date: \_\_\_\_\_ Email: kmoran@bry-consultant.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

**API NUMBER**

05 045 13104 00

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

**CONDITIONS OF APPROVAL, IF ANY:** \_\_\_\_\_

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

**Attachment Check List**

Att Doc Num	Name	Doc Description
400095136	OTHER	Diesel Use and Cuttings Procedure.PDF
400095137	MINERAL LEASE MAP	Encana Mineral Lease Map.PDF
400095138	PLAT	Long Ridge 01D P15-595 Plat.pdf
400095139	TOPO MAP	LONG RIDGE P15-595 - Topo Map.pdf
400095184	30 DAY NOTICE LETTER	P15 30 Day Letter - Sent 9-22-2010.PDF
400101661	DEVIATED DRILLING PLAN	Berry Petroleum (SESE P15 595) LR01D Plan #1.pdf

Total Attach: 6 Files