

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refilling
Sidetrack

Document Number:
2590353
Plugging Bond Surety
20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC 4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700
City: DENVER State: CO Zip: 80202-5632

6. Contact Name: JEVIN CROTEAU Phone: (720)876-5339 Fax: (720)876-6339
Email: JEVIN.CROTEAU@ENCANA.COM

7. Well Name: PRATT Well Number: 0-2-29

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8582

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 29 Twp: 1N Rng: 68W Meridian: 6
Latitude: 40.028140 Longitude: -105.035670

Footage at Surface: 408 FNL/FSL FNL 393 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 5116 13. County: WELD

14. GPS Data:

Date of Measurement: 06/02/2010 PDOP Reading: 1.4 Instrument Operator's Name: TOM WINANS

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1320 FNL 50 FWL FWL Bottom Hole: FNL/FSL 1320 FNL 50 FWL FWL
Sec: 29 Twp: 1N Rng: 68W Sec: 29 Twp: 1N Rng: 68W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 429 ft

18. Distance to nearest property line: 393 ft 19. Distance to nearest well permitted/completed in the same formation: 899 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407	160	GWA
J SAND	JSND	232-23	160	GWA
NIOBRARA	NBRR	407	160	GWA

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: 20090011

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
W2NW OF SEC. 29, T1N, R68W

25. Distance to Nearest Mineral Lease Line: 50 ft 26. Total Acres in Lease: 80

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite
Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	900	390	900	0
1ST	7+7/8	4+1/2	11.6	8,582	310	8,582	7,397

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments NO CONDUCTOR CASING WILL BE USED. PROPOSED GWA UNIT CONFIGURATION FOR JSND AND NB-CD: W2NW OF SEC. 29 & E2NE OF SEC. 30 ; Encana Oil & Gas (USA) Inc. requests approval of a Rule 318Aa and Rule 318Ac exception location: Wellhead is to be located outside of a GWA drilling window.

34. Location ID: 329735

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JEVIN CROTEAU

Title: REGULATORY Date: 9/27/2010 Email: JEVIN.CROTEAU@ENCANA.C

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin Director of COGCC Date: 10/21/2010

API NUMBER
05 123 32377 00

Permit Number: _____ Expiration Date: 10/20/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
2511440	DEVIATED DRILLING PLAN	LF@2547253 2511440
2590353	APD ORIGINAL	LF@2547248 2590353
2590354	WELL LOCATION PLAT	LF@2547249 2590354
2590355	TOPO MAP	LF@2547250 2590355
2590356	MINERAL LEASE MAP	LF@2547251 2590356
2590357	30 DAY NOTICE LETTER	LF@2547252 2590357
2590359	EXCEPTION LOC REQUEST	LF@2547254 2590359
2590360	EXCEPTION LOC WAIVERS	LF@2547255 2590360
2590361	PROPOSED SPACING UNIT	LF@2547256 2590361

Total Attach: 9 Files

Error: Subreport could not be shown.