

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400097824

Plugging Bond Surety

20040071

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

 OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒
Refiling ☐Sidetrack ☐3. Name of Operator: ANTERO RESOURCES PICEANCE CORPORATION4. COGCC Operator Number: 100795. Address: 1625 17TH ST STE 300City: DENVER State: CO Zip: 802026. Contact Name: Hannah Knopping Phone: (303)357-6412 Fax: (303)357-7315Email: hknopping@anteroresources.com7. Well Name: BAT Well Number: 34D-18-07-95

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 6390

## WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 18 Twp: 7S Rng: 95W Meridian: 6Latitude: 39.431065 Longitude: -108.033243
 Footage at Surface: 233 FNL/FSL FSL 824 FEL/FWL FEL
11. Field Name: Parachute Field Number: 6735012. Ground Elevation: 5441 13. County: GARFIELD

## 14. GPS Data:

Date of Measurement: 09/17/2010 PDOP Reading: 3.0 Instrument Operator's Name: Elwood Barry Giles15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL 117 FSL 1960 FEL/FWL FEL Bottom Hole: FNL/FSL 117 FSL 1960 FEL/FWL FEL  
 Sec: 18 Twp: 7S Rng: 95W Sec: 18 Twp: 7S Rng: 95W
16. Is location in a high density area? (Rule 603b)? ☒ Yes ☐ No17. Distance to the nearest building, public road, above ground utility or railroad: 430 ft18. Distance to nearest property line: 497 ft 19. Distance to nearest well permitted/completed in the same formation: 299 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	440-60	320	S/2
Williams Fork	WMFK	440-60	320	S/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See attached mineral lease map

25. Distance to Nearest Mineral Lease Line: 117 ft 26. Total Acres in Lease: 80

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Onsite if meet Tbl 910

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	16	55#	60	177	60	0
SURF	12+1/4	8+5/8	24/32#	2,200	834	2,200	0
1ST	7+7/8	4+1/2	11.6#	6,390	657	6,390	

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments First String/Production TOC will be >200 feet above Top of Gas. NOTE: Antero Resources (applicant) is the surface owner of the SESE of Section 18-T7S-R95W and a portion of the N2NENE of Section 19-T7S-R95W, where the subject well pad will be located and therefore no 30-Day Letter or SUA have been attached. #24-The well distance given is to a lease line within the drilling and spacing unit. BHL complies with spacing order with respect to distance to unit boundary.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Hannah Knopping

Title: Permit Representative Date: \_\_\_\_\_ Email: hknopping@anteroresources.co

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

API NUMBER

05

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**Attachment Check List**

Att Doc Num	Name	Doc Description
400097850	MINERAL LEASE MAP	Mineral Lease Map - Antero-Exxon et al (80 acres).pdf
400097851	WELL LOCATION PLAT	BAT 34D-18-07-95 Plat.pdf
400102064	DEVIATED DRILLING PLAN	Antero BAT 34D-18-07-95 P01.pdf
400104013	TOPO MAP	Monument Ridge_Access Road Map.pdf

Total Attach: 4 Files