



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198321

Date 8/15/2010	Well Owner KERR/McGEE	Well No. 24-33	Lease CANNON
County WELD	State COLORADO	Field	
Charge to KERR/McGEE OIL & GAS ONSHORE, LP	Charge Code		For Office Use Only
Address 1999 BROADWAY, STE. 3700 (PATTERSON #189)			
City, State DENVER, COLORADO 80202			
Pump Truck No. 1201	Code	Bulk Truck No. 1204/1201	Code
Type of Job	Depth	Ft. 840	To
Surface 8 5/8" CSO-24"	Bottom of Surface	Ft. 834	To
Plug	Plug Landed @ 790	Ft. Time On 2200	
Production	Pipe Landed @ 834	Ft. Time Off	PLUG LANDED 0248

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Near TYPE III	530	SXS		
	Poz. Mix				
	Calcium Chloride	2.5%			
	Gel % Flo-Cele 1/4" Per Sack				
	Handling Charge				
	Hauling Charge				
	Additional Cement				
	MIXING RATE 4BPM			PRE-FLUSH 0209-0212	
	DISP RATE 5BPM			MIX 0212-0235	
	TOTAL SLURRY VOL 124.5 BBLs CEMENT			CHANGE VALVES 0235-0238	
	SLURRY VOL 1.32 FT³/SK			DISPLACE 0238-0239-0248	
	SLURRY WT 14.9-15.0 PPG			MIKE LINGRENDAL LIFT 638	
	WATER/CEMENT 6.25 GAL/SK				
	PLUG LANDED @ 640 PSI			User ID ZMDLB	
	WATER TEMP 73			WBS/VOIC 201 2092	

PRE-FLUSH W/ 20 BBLIS H ₂ O	Tax Reference Code	Sub-Total
DISPLACE W/ 50 BBLIS H ₂ O	State CO 2.9 Gr. Acct.	800/2040
CIRCULATE 9 BBLIS CEMENT	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		34			
1201/1214		Bulk Truck		34/34	1	1	

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **Jim/Sam/Oscar/Travis**

Received By

Customer or His Agent