

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE

ET

OE

ES

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐Refiling ☐Sidetrack ☐

Document Number:

400085728

Plugging Bond Surety

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY

4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000

City: DENVER State: CO Zip: 80202

6. Contact Name: Greg Davis Phone: (303)606-4071 Fax: (303)629-8268

Email: Greg.J.Davis@Williams.com

7. Well Name: ExxonMobil Well Number: GM 444-22

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 7600

WELL LOCATION INFORMATION

10. QtrQtr: Lot 1 Sec: 27 Twp: 6S Rng: 96W Meridian: 6

Latitude: 39.499774 Longitude: -108.087714

Footage at Surface: 975 FNL/FSL FNL 706 FEL/FWL FEL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 5770 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 09/29/2008 PDOP Reading: 3.0 Instrument Operator's Name: Geoffrey Pappas

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
598 FSL 735 FEL 598 FSL 735 FEL
Sec: 22 Twp: 6S Rng: 96W Sec: 22 Twp: 6S Rng: 96W16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 5395 ft

18. Distance to nearest property line: 1015 ft 19. Distance to nearest well permitted/completed in the same formation: 330 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	510-20		Unspaced

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC34553

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See Attached

25. Distance to Nearest Mineral Lease Line: 598 ft 26. Total Acres in Lease: 419

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-use and evaporation

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	18	48#	45	25	45	0
SURF	13+1/2	9+5/8	32.3#	957	334	957	0
1ST	7+7/8	4+1/2	11.6#	7,600	559	7,600	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Cement 200' above uppermost mvrd sand. COC34553

34. Location ID: 311557

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Greg Davis

Title: Supervisor Permits Date: _____ Email: Greg.J.Davis@Williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name	Doc Description
400086948	LEGAL/LEASE DESCRIPTION	Lease COC34553.pdf
400101451	WELL LOCATION PLAT	GM 444-22 Well Location Plat.pdf
400101453	SURFACE AGRMT/SURETY	MV 23-27 SUA.pdf
400102312	TOPO MAP	MV 23-27 Topo Map.pdf
400103810	DEVIATED DRILLING PLAN	GM 444-22 Directional Plot and Plan.pdf
400104584	FED. DRILLING PERMIT	GM 444-22 Federal Drilling Permit.pdf

Total Attach: 6 Files