



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198480

| | | | |
|---|------------------------------|---------------------------------|------------------------------------|
| Date <u>9/25/10</u> | Well Owner <u>Kerr McGee</u> | Well No. <u>7-2</u> | Lease <u>Highway 160</u> |
| County <u>Weld</u> | State <u>Colorado</u> | Field | |
| Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u> | Charge Code | | |
| Address <u>1999 Broadway, Suite 3700 (Vtreme #8)</u> | For Office Use Only | | |
| City, State <u>Denver Colorado 80202</u> | | | |
| Pump Truck No. <u>1208</u> | Code | Bulk Truck No. <u>1217/1216</u> | Code |
| Type of Job | | Depth | Ft. <u>1206</u> |
| Surface <u>8 5/8" CSG-54"</u> | | Bottom of Surface | Ft. <u>1196</u> |
| Plug | | Plug Landed @ <u>1152</u> | Ft. Time On <u>1745</u> |
| Production | | Pipe Landed @ <u>1196</u> | Ft. Time Off <u>Plug Down 2100</u> |

| Reference No. | Description | Qty. | Meas. | Unit Price | Amount |
|---------------|--|--------------|-------------|-----------------------|--------|
| | Pump Truck Charge | | | | |
| | Cement Neat <u>✓ Type III</u> | <u>750</u> | <u>SKS</u> | | |
| | Poz. Mix | | | | |
| | Calcium Chloride | <u>2.5%</u> | | | |
| | Gel % Flo-Cele <u>1</u> #Per Sack | | | | |
| | Handling Charge | | | | |
| | Hauling Charge | | | | |
| | Additional Cement | | | | |
| | Mixing Rate - <u>4 BPM</u> Pre-Flush | <u>2003-</u> | <u>2009</u> | <u>2017 9/15. DR2</u> | |
| | Disp. Rate - <u>5 BPM</u> Mixing | <u>2009-</u> | <u>2042</u> | <u>80012090</u> | |
| | Slurry Vol - <u>1.2 cu ft/sk</u> Change Valves | <u>2042-</u> | <u>2045</u> | | |
| | Slurry WT <u>14.5-15.0 PPG</u> Disp. | <u>2045-</u> | <u>2100</u> | | |
| | Water/Cement - <u>6.25 Gall/sk</u> | | | | |
| | Water Temp <u>60°F</u> | | | | |
| | Total Slurry Vol <u>176 BBLs Cement</u> | | | | |
| | Landed Plug @ <u>575 PSI</u> | | | | |

| | | | | | | | |
|---|-----------------------|---------------|----------|--------------|---------|-------|---------------|
| Remarks: <u>Pre-Flush w/ 30 BBLs H₂O</u> | Tax Reference Code | Sub Total | | | | | |
| <u>Displace w/ 73 BBLs H₂O</u> | State <u>CO 2.9 %</u> | Tax | | | | | |
| <u>Circulate 4 BBLs Cement</u> | Disc. | Total | | | | | |
| Truck No. | Code | State Mileage | Nebraska | Colorado | Wyoming | Other | Total Mileage |
| <u>1208</u> | | Pump Truck | | <u>64</u> | | | |
| <u>1217/1216</u> | | Bulk Truck | | <u>64/64</u> | | | |

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Steve & Dallas

Received By Meg Horvath
Customer or His Agent

Prepared by: CEMENTERS WELL SERVICE

Company Name: KERR MCGEE OIL&GAS XTREME#8

Well Name: HIGHWAY 160 7-2

Field:

Formation:

County: WELD

State: CO

Job Date: 09/25/10

Comments: TD@1206 SET@1196

PLUG LANDED@1152

Fluids: PRE-FLUSH 30BBLS H2O DISP 73 BBLS H2O

Proppants:

Average Rate: 4 BPM

Average STP:

Tubing: N/A

Casing: 8 5/8

Packer:

Filename: 10092501

Closure Pres: 4000

LINEAR PLOT

