

Abyssiis C34-99HZ
Production Facility
4N,64W,S34
SE/4SE/4

Map Unit Description

Weld County, Colorado, Southern Part

4 Aquolls and Aquepts, flooded

Setting

Elevation: 3600 to 4700 feet
Mean annual precipitation: 12 to 16 inches
Mean annual air temperature: 50 to 55 degrees F
Frost-free period: 100 to 165 days

Composition

Aquolls and similar soils: 55 percent
Aquepts, flooded, and similar soils: 25 percent
Minor components: 20 percent

Description of Aquolls

Setting

Landform: Drainageways, plains, depressions
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Recent alluvium

Properties and Qualities

Slope: 0 to 3 percent
Drainage class: Poorly drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low or high (0.06 to 6.00 in/hr)
Depth to water table: About 6 to 36 inches
Frequency of flooding: Frequent
Frequency of ponding: None
Calcium carbonate maximum: 10 percent
Gypsum maximum: 0 percent
Salinity maximum: Slightly saline or moderately saline (8.0 to 16.0 mmhos/cm)
Sodium adsorption ratio maximum: 5.0
Available water capacity: Low (about 4.7 inches)

Interpretive Groups

Land capability classification (irrigated): 6w
Land capability (non irrigated): 6w
Ecological site: Salt Meadow (R067BY035CO)

Typical Profile

0 to 8 inches: variable
8 to 60 inches: stratified sandy loam to clay

Description of Aquepts, flooded

Setting

Landform: Stream terraces
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Recent alluvium

Properties and Qualities

Slope: 0 to 3 percent
Drainage class: Poorly drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low or high (0.06 to 6.00 in/hr)
Depth to water table: About 6 to 36 inches
Frequency of flooding: Frequent
Frequency of ponding: None
Calcium carbonate maximum: 10 percent
Gypsum maximum: 0 percent
Salinity maximum: Slightly saline or moderately saline (8.0 to 16.0 mmhos/cm)
Sodium adsorption ratio maximum: 5.0
Available water capacity: Low (about 4.7 inches)

Interpretive Groups

Land capability classification (irrigated): 6w
Land capability (non irrigated): 6w

Map Unit Description

Weld County, Colorado, Southern Part

Ecological site: Wet Meadow (R067BY038CO)

Typical Profile

0 to 8 inches: variable

8 to 60 inches: stratified sandy loam to clay

Minor Components

Thedalund

Percent of map unit: 10 percent

Haverson

Percent of map unit: 10 percent

Aloysius C34-99HZ
Production Facility
4N, 64W, S34
SE/4SE/4

Map Unit Description

Weld County, Colorado, Southern Part

41 Nunn clay loam, 0 to 1 percent slopes

Setting

Elevation: 4550 to 5150 feet
Mean annual precipitation: 12 to 18 inches
Mean annual air temperature: 46 to 54 degrees F
Frost-free period: 115 to 180 days

Composition

Nunn and similar soils: 85 percent
Minor components: 15 percent

Description of Nunn

Setting

Landform: Plains, terraces
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Mixed alluvium and/or eolian deposits

Properties and Qualities

Slope: 0 to 1 percent
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low or moderately high (0.06 to 0.20 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 15 percent
Gypsum maximum: 0 percent
Available water capacity: High (about 9.1 inches)

Interpretive Groups

Land capability classification (irrigated): 2e
Ecological site: Clayey Plains (R067BY042CO)

Typical Profile

0 to 9 inches: clay loam
9 to 29 inches: clay loam
29 to 60 inches: sandy loam

Minor Components

Heldt

Percent of map unit: 7 percent

Dacono

Percent of map unit: 4 percent

Altvan

Percent of map unit: 4 percent

Aloysius C34-99 HZ
Production Facility
4N, 64W, S34
SE/4SE/4

Map Unit Description

Weld County, Colorado, Southern Part

70 Valent sand, 3 to 9 percent slopes

Setting

Elevation: 4650 to 5100 feet
Mean annual precipitation: 13 to 19 inches
Mean annual air temperature: 48 to 52 degrees F
Frost-free period: 130 to 180 days

Composition

Valent and similar soils: 95 percent
Minor components: 5 percent

Description of Valent

Setting

Landform: Plains
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Eolian deposits

Properties and Qualities

Slope: 3 to 9 percent
Drainage class: Excessively drained
Capacity of the most limiting layer to transmit water (Ksat): High or very high (5.95 to 19.98 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 0 percent
Gypsum maximum: 0 percent
Available water capacity: Very low (about 2.6 inches)

Interpretive Groups

Land capability classification (irrigated): 4e
Land capability (non irrigated): 6e
Ecological site: Deep Sand (R067BY015CO)

Typical Profile

0 to 8 inches: fine sand
8 to 60 inches: sand

Minor Components

Osgood

Percent of map unit: 5 percent