

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:
400074768
Plugging Bond Surety
20030009

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

3. Name of Operator: NOBLE ENERGY INC 4. COGCC Operator Number: 100322
5. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
6. Contact Name: JAN KAJIWARA Phone: (303)228-4092 Fax: (303)228-4286
Email: jkajiwara@nobleenergyinc.com
7. Well Name: NCLP PC AA Well Number: 08-07D
8. Unit Name (if appl): _____ Unit Number: _____
9. Proposed Total Measured Depth: 7138

WELL LOCATION INFORMATION

10. QtrQtr: SEW Sec: 8 Twp: 6N Rng: 63W Meridian: 6
Latitude: 40.502510 Longitude: -104.462500
Footage at Surface: _____ FNL/FSL _____ FEL/FWL _____
2129 FNL 2166 FWL
11. Field Name: WATTENBERG Field Number: 90750
12. Ground Elevation: 4711 13. County: WELD

14. GPS Data:

Date of Measurement: 06/14/2010 PDOP Reading: 2.1 Instrument Operator's Name: ROBERT DALEY

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____
1980 FNL 1980 FEL 1980 FNL 1980 FEL
Sec: 8 Twp: 6N Rng: 63W Sec: 8 Twp: 6N Rng: 63W

16. Is location in a high density area? (Rule 603b)? Yes No
17. Distance to the nearest building, public road, above ground utility or railroad: 1245 ft
18. Distance to nearest property line: 2025 ft 19. Distance to nearest well permitted/completed in the same formation: 970 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL		80	W/2NE4
NIOBRARA	NBRR		80	W/2NE4

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
N/2, SW/4, W/2SE/4 T6N-R63W-SECTION 8

25. Distance to Nearest Mineral Lease Line: 655 ft 26. Total Acres in Lease: 560

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: CLOSED LOOP SYSTEM

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	500	210	500	0
1ST	7+7/8	4+1/2	11.6	6,979	618	6,979	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments NO CONDUCTOR CASING WILL BE USED. TOC=200' ABOVE THE NIOBRARA. PAD WITH NCLP PC AA08-17D (400074770)

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JAN KAJIWARA

Title: REGULATORY ANALYST Date: 10/22/2010 Email: jkajiwara@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 11/13/2010

API NUMBER
05 123 32546 00

Permit Number: _____ Expiration Date: 11/12/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hr notice of spud to Bo Brown at 970-330-6085 or email at bo.brown@state.co.us.
- 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
- 3) If completed, provide cement coverage from the first casing shoe to a minimum of 200' above Niobrara. Verify cement with a cement bond log.
- 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
2512843	SURFACE CASING CHECK	LF@2611038 2512843
400074768	FORM 2 SUBMITTED	LF@2607175 400074768
400091383	30 DAY NOTICE LETTER	LF@2607176 400091383
400091386	DEVIATED DRILLING PLAN	LF@2607177 400091386
400091391	WELL LOCATION PLAT	LF@2607179 400091391

Total Attach: 5 Files

Error: Subreport could not be shown.