

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

Document Number:
400089271
Plugging Bond Surety
20030009

3. Name of Operator: NOBLE ENERGY INC 4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202

6. Contact Name: JAN KAJIWARA Phone: (303)228-4092 Fax: (303)228-4286
Email: jkajiwara@nobleenergyinc.com

7. Well Name: Wells Ranch PC AA Well Number: 22-18

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7000

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 22 Twp: 6N Rng: 63W Meridian: 6
Latitude: 40.475770 Longitude: -104.423200

Footage at Surface: 1296 FNL/FSL FNL 2600 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4740 13. County: WELD

14. GPS Data:

Date of Measurement: 07/27/2010 PDOP Reading: 2.0 Instrument Operator's Name: John C. Barickman

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 1292 ft

18. Distance to nearest property line: 30 ft 19. Distance to nearest well permitted/completed in the same formation: 832 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CODL		160	GWA
Niobrara	NBRR		160	GWA

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Section 22 T6N R63W: NW/4

25. Distance to Nearest Mineral Lease Line: 30 ft 26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24#	500	210	500	0
1ST	7+7/8	4+1/2	11.6#	7,000	621	7,000	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments NO CONDUCTOR CASING WILL BE USED. 1ST STRING TOP OF CEMENT = 200' ABOVE NIOBRARA. UNIT CONFIGURATION = W/2NE/4 & E/2NW/4 for Codell and Niobrara. Noble requests approval of a Rule 318Aa : Wellhead is to be located outside of a GWA drilling window. Waiver attached. Waivers attached. Noble requests approval of a Rule 603.a.(2) exception location: Wellhead is to be located less than 150' from a property line. Waiver attached.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JAN KAJIWARA

Title: REGULATORY ANALYST Date: 10/19/2010 Email: jkajiwara@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 11/13/2010

API NUMBER
05 123 32554 00

Permit Number: _____ Expiration Date: 11/12/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

-) Provide 24 hr notice of spud to Bo Brown at 970-330-6085 or email at bo.brown@state.co.us.
- 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
- 3) If completed, provide cement coverage from the first casing shoe to a minimum of 200' above Niobrara. Verify cement with a cement bond log.

Attachment Check List

Att Doc Num	Name	Doc Description
1726237	SURFACE CASING CHECK	LF@2610417 1726237
2529830	CORRESPONDENCE	LF@2610184 2529830
2529832	EXCEPTION LOC REQUEST	LF@2612333 2529832
400089271	FORM 2 SUBMITTED	LF@2605872 400089271
400091671	30 DAY NOTICE LETTER	LF@2605873 400091671
400091673	PLAT	LF@2605874 400091673
400091676	EXCEPTION LOC WAIVERS	LF@2605875 400091676
400091678	EXCEPTION LOC REQUEST	LF@2605876 400091678
400091693	EXCEPTION LOC WAIVERS	LF@2605877 400091693
400101724	SURFACE AGRMT/SURETY	LF@2605878 400101724

Total Attach: 10 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	received request letter	11/2/2010 9:04:00 AM
Permit	Need property line encroachment request letter	11/2/2010 7:54:10 AM

Total: 2 comment(s)

Error: Subreport could not be shown.