

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400099262

Plugging Bond Surety

20030110

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: WHITING OIL AND GAS CORPORATION

4. COGCC Operator Number: 96155

5. Address: 1700 BROADWAY STE 2300

City: DENVER State: CO Zip: 80290

6. Contact Name: Scott Webb Phone: (303)390-4095 Fax: (303)390-4960
Email: scottw@whiting.com

7. Well Name: Boies Well Number: C-27K-J1

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 10102

WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 27 Twp: 2S Rng: 98W Meridian: 6

Latitude: 39.845982 Longitude: -108.381309

Footage at Surface: 2239 FNL/FSL FSL 2607 FEL/FWL FWL

11. Field Name: Sulphur Creek Field Number: 80090

12. Ground Elevation: 6436 13. County: RIO BLANCO

14. GPS Data:

Date of Measurement: 11/05/2008 PDOP Reading: 1.7 Instrument Operator's Name: D. Petty

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2415 FSL 1864 FEL 2415 FEL 1864 FEL
Sec: 27 Twp: 2S Rng: 98W Sec: 27 Twp: 2S Rng: 98W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 384 ft

18. Distance to nearest property line: 416 ft 19. Distance to nearest well permitted/completed in the same formation: 580 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	527-4		
Sego	SEGO	527-4		
Williams Fork	WMFK	527-1		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
A lease map is on file with the COGCC.

25. Distance to Nearest Mineral Lease Line: 524 ft 26. Total Acres in Lease: 1160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	26	54	100			
SURF	12+1/4	9+5/8	40	3,500	922	3,500	0
1ST	8+1/2	4+1/2	11.6	10,102	879	10,102	3,400

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments The pad has been constructed. The reserve pit has been constructed. The re-file will not require any expansion or additional surface disturbance of the pad. The location does not require a variance from any of the rules listed in Rule 306.d.(1).(A).(ii). The location is not in a wildlife restricted surface occupancy area.

34. Location ID: 335975

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Scott M. Webb

Title: Regulatory Coordinator Date: 10/11/2010 Email: scottw@whiting.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 11/13/2010

API NUMBER

05 103 11300 00

Permit Number: _____ Expiration Date: 11/12/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) CEMENT-TOP VERIFICATION BY CBL REQUIRED.

(3) RESERVE PIT MUST BE LINED.

(4) OPERATOR MUST ENSURE 110 PERCENT SECONDARY CONTAINMENT FOR ANY VOLUME OF FLUIDS CONTAINED AT WELL-SITE DURING DRILLING AND COMPLETION OPERATIONS. IF FLUIDS ARE CONVEYED VIA PIPELINE, OPERATOR MUST IMPLEMENT BEST-MANAGEMENT-PRACTICES TO CONTAIN ANY UNINTENTIONAL RELEASE OF FLUIDS.

(5) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

(6) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST DEDICATED* WATER WELL WITHIN 1-MILE IS 00 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400099262	FORM 2 SUBMITTED	LF@2600704 400099262
400099317	WELL LOCATION PLAT	LF@2600705 400099317

Total Attach: 2 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Changed zone type to multiple and added location id	11/3/2010 4:48:06 PM
Permit	Corrected Qtr/Qtr to NESW with Opr-Scott's permission. sbf	10/12/2010 2:25:41 PM

Total: 2 comment(s)

Error: Subreport could not be shown.