



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198202

| | | | |
|--|------------------------------|---------------------------------|------------------------------------|
| Date <u>6/26/10</u> | Well Owner <u>KEER McGEE</u> | Well No. <u>35-9</u> | Lease <u>NRC</u> |
| County <u>Weld</u> | State <u>Colorado</u> | Field | |
| Charge to <u>KEER McGEE O.I. Gas Onshore, LP</u> | | | Charge Code |
| Address <u>1999 Broadway, Suite 3700 (Xtreme #7)</u> | | | For Office Use Only |
| City, State <u>Denver, Colorado 80202</u> | | | |
| Pump Truck No. <u>1208</u> | Code | Bulk Truck No. <u>1214/1216</u> | Code |
| Type of Job | | Depth | Ft. <u>1028</u> |
| Surface <u>8 5/8" CSG-34"</u> | | Bottom of Surface | Ft. <u>1017</u> |
| Plug | | Plug Landed @ <u>973</u> | Ft. Time On <u>0215</u> |
| Production | | Pipe Landed @ <u>1017</u> | Ft. Time Off <u>Plug Down 0715</u> |

| Reference No. | Description | Qty. | Meas. | Unit Price | Amount |
|---------------|-------------------------------------|----------------------|--------------|-----------------|--------------------|
| | Pump Truck Charge | | | | |
| | Cement Neat <u>✓ Type III</u> | <u>640</u> | <u>SKS</u> | | |
| | Poz. Mix | | | | |
| | Calcium Chloride | <u>25%</u> | | | |
| | Gel % Flo-Cele <u>1/4</u> #Per Sack | | | | |
| | Handling Charge | | | | <u>2045777 DRL</u> |
| | Hauling Charge | | | | |
| | Additional Cement | | | <u>800/2090</u> | |
| | Mixing Rate -4 BPM | <u>Pre-Flush</u> | <u>0626-</u> | <u>0632</u> | |
| | Disp. Rate -5 BPM | <u>Mixing</u> | <u>0633-</u> | <u>0700</u> | |
| | Slurry Vol -1 3/4 CU FT/SK | <u>Change Valves</u> | <u>0700-</u> | <u>0703</u> | |
| | Slurry WT 14.8-15.0 PPG | <u>Disp.</u> | <u>0703-</u> | <u>0715</u> | |
| | Water/Cement -6.25 Gal/SK | | | | |
| | Water Temp 60°F | | | | |
| | Total Slurry Vol 150 BBLs Cement | | | | |
| | Landed Plug @ 425 PSI | | | | |

| | | |
|---|----------------------|-----------|
| Remarks: <u>Pre-Flush w/ 30 BBLs H²O</u> | Tax Reference Code | Sub Total |
| <u>Displace w/ 60 BBLs H²O</u> | State <u>10.29</u> % | Tax |
| <u>Circulate 5 BBLs Cement</u> | Disc. | Total |

| Truck No. | Code | State Mileage | Nebraska | Colorado | Wyoming | Other | Total Mileage |
|------------------|------|---------------|----------|--------------|---------|-------|---------------|
| <u>1208</u> | | Pump Truck | | <u>84</u> | | | |
| <u>1214/1216</u> | | Bulk Truck | | <u>84/84</u> | | | |

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Steve & Dallas

Received By

Rusty Tucker
Customer or His Agent

Prepared by: CEMENTERS WELL SERVICE

Company Name: KERR MCGEE OIL&GAS XTREME #7

Well Name: NRC 35-9

Field:

Formation:

County: WELD

State: CO

Job Date: 06/26/10

Comments: TD@1028 SET1017

PLUG LANDED@973

Fluids: PRE-FLUSH 30BBLS DISP 62BBLS

Proppants:

Average Rate: 4 BPM

Average STP:

Tubing: N/A

Casing: 8 5/8

Packer:

Filename: 10062601

Closure Pres: 4000

LINEAR PLOT

