

Berry Petroleum Company
Chevron 6-7D
API # 05-045-17274-0000
NWSE Sec 06 Twn 6S Rng 96W
Garfield County, Colorado

Prepared Charles Durkoop
Updated 7/15/2010

Rig Patterson 302

8169 KB
8147 GL
22 KB-GL

249 BHT

TOC @ 2874'

TOCC @ 7438'

1/31/2010 Spud
2/4/2010 Set Surf
2/13/2010 Set Prod
8/9/2010 PTST 7000# @ PBDT
8/13/2010 Frac Stgs 1-7
8/16/2010 CT D/O CFPs

20" Conductor @ 100'

16" hole @ 2575'

56 jts 9-5/8" 36# J-55 surf csg @ 2508' w/ PS, inj port @ 2370'
cmdt 1551 sx lead @ 12.3 ppg and 100 sx tail @ 14.2 ppg

Equipment in Hole	Qty	Length	Depth
KB		22.00	22.00
			22.00
			22.00
			22.00
			22.00
			22.00

Stage 7: 7839 - 8017', total 32 holes @ 2 spf
Frac'd 145550 lbs 30/50 white sand, 6913 bbl slickwater, 500 g 7.5% acid

Stage 6: 8073 - 8299', total 34 holes @ 2 spf
Frac'd 153368 lbs 30/50 white sand, 7634 bbl slickwater, 500 g 7.5% acid

Stage 5: 8392 - 8569', total 16 holes @ 2 spf
Frac'd 57959 lbs 30/50 white sand, 3094 bbl slickwater, 500 g 7.5% acid

Stage 4: 8602 - 8834', total 24 holes @ 2 spf
Frac'd 96369 lbs 30/50 white sand, 4628 bbl slickwater, 500 g 7.5% acid

Stage 3: 9153 - 9349', total 30 holes @ 2 spf
Frac'd 153671 lbs 30/50 white sand, 7594 bbl slickwater, 500 g 7.5% acid

Stage 2: 9405 - 9602', total 24 holes @ 2 spf
Frac'd 111598 lbs 30/50 white sand, 4736 bbl slickwater, 500 g 7.5% acid

Stage 1: 9644 - 9867', total 22 holes @ 2 spf
Frac'd 102733 lbs 30/50 white sand, 4924 bbl slickwater, 500 g 7.5% acid

Marker Jts @
5019 - 41' & 7618 - 42'

8-3/4" hole @ 8816' & 7-7/8" hole @ 10213'
229 jts 4-1/2" 11.6# P-110 prod csg @ 10180', FC @ 10140'
cmdt 764 sx Type III @ 12.5 ppg & 2.50 yield

PBDT @ 10100' WL Tag 2/25/10
CT C/O @ 10100' on 8/16/10