

FORM
5
Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

DRILLING COMPLETION REPORT

Document Number:
400103236

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

1. OGCC Operator Number: 66571 4. Contact Name: Joan Proulx
2. Name of Operator: OXY USA WTP LP Phone: (970) 263.3641
3. Address: P O BOX 27757 Fax: (970) 263.3694
City: HOUSTON State: TX Zip: 77227

5. API Number 05-045-17605-00 6. County: GARFIELD
7. Well Name: CASCADE CREEK Well Number: 697-16-27A
8. Location: QtrQtr: NWSW Section: 16 Township: 6S Range: 97W Meridian: 6
Footage at surface: Distance: 2242 feet Direction: FSL Distance: 787 feet Direction: FWL
As Drilled Latitude: 39.521900 As Drilled Longitude: -108.231340

GPS Data:

Data of Measurement: 10/08/2010 PDOP Reading: 2.3 GPS Instrument Operator's Name: J. Grabowski

** If directional footage

at Top of Prod. Zone Distance: 1977 feet Direction: FNL Distance: 1898 feet Direction: FWL
Sec: 16 Twp: 6S Rng: 97W
at Bottom Hole Distance: 1997 feet Direction: FNL Distance: 1860 feet Direction: FWL
Sec: 16 Twp: 6S Rng: 97W

9. Field Name: GRAND VALLEY 10. Field Number: 31290

11. Federal, Indian or State Lease Number: _____

12. Spud Date: (when the 1st bit hit the dirt) 03/22/2010 13. Date TD: 04/23/2010 14. Date Casing Set or D&A: 04/24/2010

15. Well Classification:

Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

16. Total Depth MD 8813 TVD 8596 17 Plug Back Total Depth MD 8757 TVD 8540

18. Elevations GR 8312 KB 8342

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

Reservoir Saturation Tool/Inelastic/Capture Mode/GR-CCL
Reservoir Saturation Tool/Sigma Mode/GR-CCL
Dipole Shear Sonic Imager
Processed Data DSI (Cased Hole)

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Top	Cement Bot	Status
CONDUCTOR	20+0/0	16+0/0	65	90	4	0	90	CALC
SURF	14+3/4	9+5/8	36	2,735	1,280	0	2,735	CALC
1ST	8+3/4	4+1/2	11.6	8,776	1,675	2,970	8,776	CBL

ADDITIONAL CEMENT

Cement work date: _____

Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
	SURF		122	0	2,735
	SURF		125	0	2,735
	SURF		122	0	2,735
	SURF		142	0	2,735
	SURF		175	0	2,735
	SURF		68	0	2,735

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WILLIAMS FORK	6,121	8,289	<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	8,289	8,684	<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	8,684		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Joan Proulx

Title: Regulatory Analyst Date: _____ Email: joan_proulx@oxy.com

Based on the information provided herein, this Drilling Completion Report (Form 5) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Attachment Check List

Att Doc Num	Name
400103242	CEMENT JOB SUMMARY
400103245	DIRECTIONAL SURVEY
400103246	LAS-
400103248	LAS-
400103249	LAS-CEMENT BOND
400103250	LAS-CEMENT BOND
400103252	LAS-
400103254	LAS-
400103259	LAS-
400103260	LAS-
400103262	LAS-

Total Attach: 11 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)