



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198556

Date 10/28/10	Well Owner KERR McGEE	Well No. 41-2	Lease Highway 160
County Weld	State Colorado		Field
Charge to KERR McGEE Oil & Gas Onshore, LP			Charge Code
Address 1999 Broadway, Suite 3700 (Xtreme #8)			For Office Use Only
City, State Denver, Colorado 80202			
Pump Truck No. 1208	Code	Bulk Truck No. 1216/1218	Code
Type of Job		Depth	Ft. 1160
Surface 8 5/8" CSG-24 #		Bottom of Surface	Ft. 1149
Plug		Plug Landed @ 1105	Ft. Time On 1305
Production		Pipe Landed @ 1149	Ft. Time Off Plug Down 1550

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat ✓ Type III	720	SKS		
	Poz. Mix				
	Calcium Chloride	2.5 %		WINE LINGREEN	
	Gel % Flo-Cele 1/4 #Per Sack			User ID ZMDL6	
	Handling Charge			WBS/WO/CC	2043404.1212
	Hauling Charge			GIL Acct	80012090
	Additional Cement				
	Mixing Rate - 4 BPM	Pre-Flush	1455-	1501	
	Disp. Rate - 5 BPM	Mixing	1501-	1533	
	Slurry Vol - 1.32 cu ft/sk	Change Valves	1533-	1536	
	Slurry WT 14.8-15.0 PPG	Disp.	1536-	1550	
	Water/Cement - 10.25 Gal/sk				
	Water Temp 50°F				
	Total Slurry Vol 169 BBLs Cement				
	Landed Plug @ 850 PSI				

Remarks: Pre-Flush w/ 30 BBLs H₂O	Tax Reference Code	Sub Total
Displace w/ 70 BBLs H₂O	State CO 2.9 %	Tax
Circulate 5 BBLs Cement	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		62			
1216/1218		Bulk Truck		62/62			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **Justin, Steve & Dallas**

Received By **Craig Jarvis**

Customer or His Agent