

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

Document Number:
400103979
Plugging Bond Surety
20030058

3. Name of Operator: EOG RESOURCES INC 4. COGCC Operator Number: 27742

5. Address: 600 17TH ST STE 1100N
City: DENVER State: CO Zip: 80202

6. Contact Name: Jennifer Yu Phone: (303)824-5576 Fax: (303)824-5576
Email: jennifer_yu@eogresources.com

7. Well Name: Critter Creek Well Number: 24-30H

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 12418

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 30 Twp: 11N Rng: 63W Meridian: 6
Latitude: 40.887078 Longitude: -104.468097

Footage at Surface: 375 feet FNL/FSL FSL 501 feet FEL/FWL FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 5264 13. County: WELD

14. GPS Data:

Date of Measurement: 09/09/2010 PDOP Reading: 0.7 Instrument Operator's Name: Robert L. Kay

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 752 FSL 793 FEL 600 FNL 2120 FEL/FWL FWL
Sec: 30 Twp: 11N Rng: 63W Sec: 30 Twp: 11N Rng: 63W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 318 ft

18. Distance to nearest property line: 375 ft 19. Distance to nearest well permitted/completed in the same formation: 2631 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	421-3	640	ALL

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See the attached lease description. 640 acres of the 4524 acres in the lease description is pertinent to the referenced well.

25. Distance to Nearest Mineral Lease Line: 600 ft 26. Total Acres in Lease: 4524

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite
Method: Land Farming Land Spreading Disposal Facility Other: Backfill and cover

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20	16	42	60	50	60	0
SURF	13+1/2	9+5/8	36	1,425	745	1,425	0
1ST	8+3/4	7	23	7,674	810	7,674	0
1ST LINER	6	4+1/2	11.6	12,418	340	12,418	6,924

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments _____

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jennifer Yu

Title: Regulatory Administrator Date: 10/28/2010 Email: jennifer_yu@eogresources.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 11/27/2010

API NUMBER 05 123 32598 00	Permit Number: _____	Expiration Date: <u>11/26/2012</u>
CONDITIONS OF APPROVAL, IF ANY: _____		

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hr notice of MIRU to Bo Brown at 970-330-6085 or email at bo.brown@state.co.us.
- 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
- 3) If completed, provide cement coverage from the intermediate casing shoe to a minimum of 200' above Niobrara. Verify cement with a cement bond log.
- 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
400103979	FORM 2 SUBMITTED
400104257	PLAT
400104258	TOPO MAP
400104259	DRILLING PLAN
400104262	DEVIATED DRILLING PLAN
400104263	LEGAL/LEASE DESCRIPTION

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)