

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400102521

Plugging Bond Surety

20090078

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☒

Sidetrack ☐

3. Name of Operator: PETROLEUM DEVELOPMENT CORPORATION

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Kelly Huffman Phone: (303)831-3974 Fax: (303)860-5838

Email: khuffman@petd.com

7. Well Name: Heinricy Well Number: 7KDU

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7632

WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 7 Twp: 5N Rng: 67W Meridian: 6

Latitude: 40.417260 Longitude: -104.939850

Footage at Surface: 1536 feet FNL/FSL FNL 1268 feet FEL/FWL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4980 13. County: WELD

14. GPS Data:

Date of Measurement: 09/30/2010 PDOP Reading: 6.0 Instrument Operator's Name: Thomas G. Carlson

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2624 FNL 1244 FWL FWL Bottom Hole: FNL/FSL 2624 FNL 1244 FWL FWL
Sec: 7 Twp: 5N Rng: 67W Sec: 7 Twp: 5N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 180 ft

18. Distance to nearest property line: 1216 ft 19. Distance to nearest well permitted/completed in the same formation: 750 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara Codell	NB-CD	407-87	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Township 5 North, Range 67 West, 6th P.M. Section 7: W/2 (and lands in other sections)

25. Distance to Nearest Mineral Lease Line: 1244 ft 26. Total Acres in Lease: 320

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	870	500	870	0
1ST	7+7/8	4+1/2	10.5	7,632	525	7,632	0

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used. The Heinrich 7AU, 7KDU, 7FDU and 7NDU will be drilled from the same pad. The wells will be tied into an existing tank battery facility approximately 390' NW of the location. Proposed GWA unit configuration for NB-CD: S2NW, N2SW ;

34. Location ID: 333325

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kelly Huffman

Title: Permit Specialist Date: 11/5/2010 Email: khuffman@petd.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 11/30/2010

API NUMBER

05 123 27131 00

Permit Number: _____ Expiration Date: 11/29/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Note surface casing setting depth change from 650' to 870'. Increase cement coverage accordingly and cement to surface. 2) Provide 24 hour notice of MIRU to Bo Brown at 970-397-4124 or e-mail at bo.brown@state.co.us. 3) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log. 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Because the distance to the nearest above ground utility is 180 feet, the derrick height shall not exceed 120 feet as measured from the ground.

Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Per Kelly Huffman, Petroleum Development Corporation concurs with derrick height COA. PVG	11/8/2010 1:56:01 PM

Total: 1 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)