

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



| | | | |
|----|----|----|----|
| DE | ET | OE | ES |
|----|----|----|----|

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

Document Number:

400106567

Plugging Bond Surety

20030058

3. Name of Operator: EOG RESOURCES INC

4. COGCC Operator Number: 27742

5. Address: 600 17TH ST STE 1100N

City: DENVER State: CO Zip: 80202

6. Contact Name: Jennifer Yu Phone: (303)824-5576 Fax: (303)824-5577
Email: jennifer_yu@eogresources.com

7. Well Name: Critter Creek Well Number: 23-19H

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 13403

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 19 Twp: 11N Rng: 63W Meridian: 6

Latitude: 40.901931 Longitude: -104.468089

Footage at Surface: 501 feet FNL/FSL 501 feet FEL/FWL FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 5288 13. County: WELD

14. GPS Data:

Date of Measurement: 01/03/2011 PDOP Reading: 0.9 Instrument Operator's Name: Robert L. Kay

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 651 FNL 642 FWL 600 FSL 600 FEL 600 FEL
Sec: 29 Twp: 11N Rng: 63W Sec: 29 Twp: 11N Rng: 63W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 492 ft

18. Distance to nearest property line: 501 ft 19. Distance to nearest well permitted/completed in the same formation: 1515 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| Niobrara | NBRR | 421-1 | 640 | ALL |

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20090114

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached lease description. Production does not pass through Section 19, T11N, R63W.

25. Distance to Nearest Mineral Lease Line: 600 ft 26. Total Acres in Lease: 1280

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Backfill and cover

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Weight Per Foot | Setting Depth | Sacks Cement | Cement Bottom | Cement Top |
|-------------|--------------|----------------|-----------------|---------------|--------------|---------------|------------|
| CONDUCTOR | 20 | 16 | 42 | 60 | 50 | 60 | 0 |
| SURF | 13+1/2 | 9+5/8 | 36 | 1,450 | 755 | 1,450 | 0 |
| 1ST | 8+3/4 | 7 | 23 | 7,723 | 820 | 7,723 | 0 |
| 1ST LINER | 6 | 4+1/2 | 11.6 | 13,403 | 390 | 13,403 | 7,081 |

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments The referenced well shares a well pad with the proposed Critter Creek 15-19H location.

34. Location ID: 420673

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jennifer Yu

Title: Regulatory Administrator Date: 11/10/2010 Email: jennifer_yu@eogresources.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 12/5/2010

| | | |
|-------------------------------|----------------------|----------------------------|
| API NUMBER 05 123 32679 00 | Permit Number: _____ | Expiration Date: 12/4/2012 |
|-------------------------------|----------------------|----------------------------|

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hr notice of MIRU to Bo Brown at 970-330-6085 or email at bo.brown@state.co.us.
- 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
- 3) If completed, provide cement coverage from the intermediate casing shoe to a minimum of 200' above Niobrara. Verify cement with a cement bond log.
- 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

| Att Doc Num | Name |
|-------------|-------------------------|
| 2565363 | SURFACE CASING CHECK |
| 400106567 | FORM 2 SUBMITTED |
| 400107495 | DRILLING PLAN |
| 400107497 | LEGAL/LEASE DESCRIPTION |
| 400107501 | PLAT |
| 400107504 | DEVIATED DRILLING PLAN |
| 400107774 | TOPO MAP |

Total Attach: 7 Files

General Comments

| <u>User Group</u> | <u>Comment</u> | <u>Comment Date</u> |
|--------------------------|---|----------------------------|
| Permit | SPACING ORDER 421-1 COVERS SECTION 29 | 11/11/2010 1:02:23 PM |
| Permit | Spacing order 421-3 does not cover section 29. Need lease map or pooling dec. | 11/11/2010 10:39:58 AM |

Total: 2 comment(s)

BMP

| <u>Type</u> | <u>Comment</u> |
|--------------------|-----------------------|
| | |

Total: 0 comment(s)