

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400114333

Plugging Bond Surety

20040105

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☒

Sidetrack ☐

3. Name of Operator: BERRY PETROLEUM COMPANY

4. COGCC Operator Number: 10091

5. Address: 1999 BROADWAY STE 3700

City: DENVER State: CO Zip: 80202

6. Contact Name: Kallasandra Moran Phone: (303)999-4225 Fax: (303)999-4325
Email: kmoran@bry-consultant.com

7. Well Name: Chevron Well Number: 6-33D

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 9959

WELL LOCATION INFORMATION

10. QtrQtr: Lot 11 Sec: 6 Twp: 6S Rng: 96W Meridian: 6

Latitude: 39.556456 Longitude: -108.153427

Footage at Surface: 2898 feet FNL/FSL FNL 1694 feet FEL/FWL FWL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 8146 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 09/08/2006 PDOP Reading: 2.4 Instrument Operator's Name: Robert Wood / Construction Surveys Inc.

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 3750 FNL 665 FWL 3750 FNL 665 FWL
Sec: 6 Twp: 6S Rng: 96W Sec: 6 Twp: 6S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 9412 ft

18. Distance to nearest property line: 665 ft 19. Distance to nearest well permitted/completed in the same formation: 279 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	510-40		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached mineral lease map.

25. Distance to Nearest Mineral Lease Line: 665 ft 26. Total Acres in Lease: 2860

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☒ Yes ☐ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Total closed loop system

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	30	20	55	90	100	90	0
SURF	16	9+5/8	36	2,000	1,000	2,000	0
1ST	8+3/4	4+1/2	11.6				200
2ND	7+7/8	4+1/2	11.6	9,959	600	9,959	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments I certify that there have been no changes on land use, lease description. Pad has been constructed. No wells have been drilled. 2 conductors have been set. No rig on site. The APD will NOT require expansion / additional surface disturbance of pad. The location does not require a variance from any of the rules listed in Rule 306.d. (1). (A). (ii). The location is not in a restricted surface occupancy area. The location is not in a sensitive wildlife habitat area for Greater Sage Grouse Production. The production casing Top of Cement will be 200' above the Top of Gas.

34. Location ID: 335887

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kallasandra M. Moran

Title: Permit Agent Date: _____ Email: kmoran@bry-consultant.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Permit Number: _____ Expiration Date: _____

API NUMBER

05 045 17235 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400114337	DEVIATED DRILLING PLAN
400114338	PLAT
400114339	TOPO MAP
400114340	MINERAL LEASE MAP
400114341	OTHER
400114342	30 DAY NOTICE LETTER

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)