

WELL LOCATION CERTIFICATE: SEKICH 35-17

SECTION 17, TOWNSHIP 3 NORTH, RANGE 67 WEST, 6TH P.M.

NW SEC. 17
2½" ALUM. CAP
LS 23501

S 89°51'46" E 2583.51'

N 89°53'44" E 2584.50'

NE SEC. 17
2½" ALUM. CAP
LS 23405

N ¼ SEC. 17
2½" ALUM. CAP
LS 19585

SURFACE LOCATION
GROUND ELEVATION= 4865'
NAD83
LATITUDE= 40.219277°
LONGITUDE= 104.912769°

NOTES:
THIS IS A DIRECTIONAL WELL
BH LOCATION TO BE 60' FSL & 1280' FWL
BH LOCATION PROVIDED BY CLIENT.
LAND SURFACE USE-IRRIGATED CROP
TWINNING PROPOSED WELL SEKICH 36-17
TO BE 10' NW
PROPOSED WELL SEKICH 36-17 TO BE
238' FSL & 2269' FEL
SEE ATTACHED MAP FOR ADDITIONAL
IMPROVEMENTS WITHIN 400'.

LATITUDE= 40°13'09.396"
LONGITUDE= 104°54'45.968"

BOTTOM HOLE LOCATION
NAD83
LATITUDE= 40.218796°
LONGITUDE= 104.918698°

LATITUDE= 40°13'07.665"
LONGITUDE= 104°55'07.312"

PDOP= 2.31
GPS OPERATOR: BEN MILIUS

(BASIS OF BEARINGS) SEE NOTE 3
N 00°16'05" W 5299.27'

17

E ¼ SEC. 17
1½" ALUM. CAP
ILLEGIBLE

S 01°01'34" E 2639.03'

S 00°07'05" E 2614.67'

SW SEC. 17
FOUND
#6 REBAR

BH- 60' FSL
1280' FWL

S 89°30'26" W 2598.09'

S ¼ SEC. 17
3¼" ALUM. CAP
LS 13155

SEKICH 36-17
SEKICH 35-17


SE SEC. 17
FOUND
STONE

S 89°30'43" W 2597.95'

WELL SEKICH 35-17 TO BE LOCATED 232' FSL AND 2261' FEL, SECTION 17, T3N, R67W OF THE 6th P.M.

LEGEND

- ⊕ = EXISTING MONUMENT
- ⊙ = PROPOSED WELL
- ⬤ = BOTTOM HOLE
- ◆ = EXISTING WELL
- BH = BOTTOM HOLE



NOTES:

1. THIS SURVEY WAS DONE BY GPS METHODS AND CONFORMS TO THE MINIMUM STANDARDS SET BY THE C.O.G.C.C., RULE NO. 215
2. ELEVATIONS SHOWN AT THE WELL HEAD, AS WELL AS HORIZONTAL CONTROL, ARE BASED ON GPS-RTK VALUES DERIVED FROM DOING 2-HOUR STATIC GPS SESSIONS AND REDUCTIONS USING O.P.U.S. SOLUTIONS.
VERTICAL = NAVD88; HORIZONTAL = NAD83/92
3. THE BEARINGS SHOWN HEREON ARE BASED ON GPS OBSERVATIONS BETWEEN THE MONUMENTS SHOWN HEREON AS FOUND ON THE FIELD DATE BELOW.
4. DISTANCES SHOWN ARE AT GROUND LEVEL, AS MEASURED IN THE FIELD, WITH TIES TO WELLS MEASURED AT A PERPENDICULAR TO SECTION LINES.

I, JERRY F. HARCEK JR., A LICENSED PROFESSIONAL LAND SURVEYOR IN THE STATE OF COLORADO DO HEREBY CERTIFY TO **KERR-MCGEE OIL & GAS ONSHORE LP**, THAT THE SURVEY AND WELL LOCATION CERTIFICATE SHOWN HEREON WERE DONE BY ME OR UNDER MY DIRECT SUPERVISION AND THAT THE DRAWING SHOWN HEREON ACCURATELY DEPICTS THE PROPOSED LOCATION OF THE WELL **SEKICH 35-17**. THIS CERTIFICATE DOES NOT REPRESENT A LAND SURVEY PLAT OR IMPROVEMENT SURVEY PLAT AS DEFINED BY C.R.S. 38-51-102 AND CANNOT BE RELIED UPON TO DETERMINE OWNERSHIP.

JERRY F. HARCEK JR., PLS 34997
COLORADO LICENSED PROFESSIONAL LAND SURVEYOR
FOR AND ON BEHALF OF P.F.S., LLC



PREPARED BY: PFS Petroleum Field Services, LLC 1801 W. 13th Ave. Denver, CO 80204	FIELD DATE: 10-20-10	WELL NAME: SEKICH 35-17
	DRAWING DATE: 10-22-10	SURFACE LOCATION: WELD COUNTY, COLORADO
BY: SMF	SW 1/4 SE 1/4, SEC. 17, T3N, R67W	

NOTICE: ACCORDING TO COLORADO LAW YOU MUST COMMENCE ANY LEGAL ACTION BASED UPON ANY DEFECT IN THIS SURVEY WITHIN THREE YEARS AFTER YOU FIRST DISCOVER SUCH DEFECT. IN NO EVENT MAY ANY ACTION BASED UPON ANY DEFECT IN THIS SURVEY BE COMMENCED MORE THAN TEN YEARS FROM THIS SAID DATE OF THIS CERTIFICATION SHOWN HEREON.