



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198539

Date 10/22/2010	Well Owner KERR/McGEE	Well No. 35-31	Lease CAMP
County WELD	State COLORADO	Field	
Charge to KERR/McGEE OIL & GAS ONSHORE, LP	Charge Code		
Address 1999 BROADWAY STE 3700 (PATERSON #189)	For Office Use Only		
City, State DENVER, COLORADO 80202			
Pump Truck No. 1201	Code	Bulk Truck No. 1217/1218	Code
Type of Job	Depth	Ft. 958	To
Surface 8 5/8" CSG-24"	Bottom of Surface	Ft. 948	To
Plug	Plug Landed @ 902	Ft.	Time On 0800
Production	Pipe Landed @ 948	Ft.	Time Off PLUG DOWN 1245

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat TYPE III	600	SKS		
	Poz. Mix				
	Calcium Chloride	2.5%	WIKI LINGREEN		
	Gel % Flo-Cele 1/4 #Per Sack		User ID ZMDL6		
	Handling Charge		WESA VOIC 2034844.DRL		
	Hauling Charge				
	Additional Cement		G/L Acct. 80012090		
	MIXING RATE 4 BPM				
	DISP RATE 5BPM				
	SLURRY VOL 1.32 CUFT/SK		PRE-FLUSH	1148-1154	
	SLURRY WT 14.8-15.0 PPG		MIX	1154-1230	
	WATER/CEMENT 6.25 GAL/SK		CHANGE VALVE	1230-1233	
	WATER TEMP 61		DISPLACE	1233-1245	
	PLUG LANDED @ 370 PST		FINAL LIFT	345	
	TOTAL SLURRY VOL 141 BBLS CEMENT				

Remarks: PRE-FLUSH w/ 20 BBLS H₂O	Tax Reference Code	Sub Total
DISPLACE w/ 57 BBLS H₂O	State CO 2.9 %	Tax
CIRCULATE 5 BBLS CEMENT	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		28			
1217/1218		Bulk Truck		28/25			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **Jim/SAM/OSCAR TRAVIS**

Received By **Suey Harrison**
Customer or His Agent