

**FORM
5**Rev
02/08State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400080841

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion1. OGCC Operator Number: 665614. Contact Name: Joan Proulx2. Name of Operator: OXY USA INCPhone: (970) 263.36413. Address: PO BOX 27757Fax: (970) 263.3694City: HOUSTON State: TX Zip: 772275. API Number 05-077-09604-006. County: MESA7. Well Name: MCDANIELWell Number: 14-4B8. Location: QtrQtr: NENW Section: 14 Township: 9S Range: 94W Meridian: 6Footage at surface: Distance: 841 feet Direction: FNL Distance: 1734 feet Direction: FWLAs Drilled Latitude: 39.281410 As Drilled Longitude: -107.853600

GPS Data:

Data of Measurement: 02/02/2009 PDOP Reading: 1.5 GPS Instrument Operator's Name: Matt Busker

** If directional footage

at Top of Prod. Zone Distance: 974 feet Direction: FNL Distance: 731 feet Direction: FWLSec: 14 Twp: 9S Rng: 94Wat Bottom Hole Distance: 1003 feet Direction: FNL Distance: 666 feet Direction: FWLSec: 14 Twp: 9S Rng: 94W9. Field Name: BRUSH CREEK10. Field Number: 7562

11. Federal, Indian or State Lease Number: _____

12. Spud Date: (when the 1st bit hit the dirt) 10/14/2008 13. Date TD: 10/22/2008 14. Date Casing Set or D&A: 10/25/2008

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation16. Total Depth MD 7490 TVD 7388 17 Plug Back Total Depth MD 7434 TVD 733218. Elevations GR 7285 KB 7309

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

Acoustic CBL, Triple Combo, borehole volume plot

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Top	Cement Bot	Status
CONDUCTOR	24+0/0	16+0/0		40	3	0	40	CALC
SURF	12+1/4	8+5/8	32	1,537	460	0	1,537	VISU
1ST	7+7/8	4+1/2	11.6	7,480	1,170	1,800	7,480	CBL

ADDITIONAL CEMENT

Cement work date: _____

Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WILLIAMS FORK	4,660	6,880	<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	6,880	7,294	<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	7,294		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Joan Proulx

Title: Regulatory Analyst Date: 9/3/2010 Email: joan_proulx@oxy.com

Based on the information provided herein, this Drilling Completion Report (Form 5) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: *David S. Nashin* Director of COGCC Date: 12/18/2010

Attachment Check List

Att Doc Num	Name
400080841	FORM 5 SUBMITTED
400080842	LAS-MUD
400080843	LAS-IND-DENS-NEU
400080844	LAS-IND-DENS-NEU
400080845	CEMENT JOB SUMMARY
400080846	DIRECTIONAL SURVEY

Total Attach: 6 Files

General Comments

User Group	Comment	Comment Date
Permit	rec Triple combo and Borehole Vol logs, doc 2547356-7	11/9/2010 11:13:57 AM
Permit	Req mud and Triple combo logs, & digital cbl log, D/S located under Well Logs Upload tab	11/5/2010 1:06:35 PM

Total: 2 comment(s)