

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

Document Number:
400117681
Plugging Bond Surety
20030058

3. Name of Operator: EOG RESOURCES INC 4. COGCC Operator Number: 27742

5. Address: 600 17TH ST STE 1100N
City: DENVER State: CO Zip: 80202

6. Contact Name: Jennifer Yu Phone: (303)824-5576 Fax: (303)824-5577
Email: jennifer_yu@eogresources.com

7. Well Name: Fiscus Mesa Well Number: 1-02H

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 10137

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 2 Twp: 9N Rng: 58W Meridian: 6

Latitude: 40.774733 Longitude: -103.823469

Footage at Surface: 501 feet FSL 501 feet FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4663 13. County: WELD

14. GPS Data:

Date of Measurement: 10/13/2010 PDOP Reading: 1.3 Instrument Operator's Name: Robert L. Kay

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
926 FSL 720 FEL 600 FNL 2639 FEL
Sec: 2 Twp: 9N Rng: 58W Sec: 2 Twp: 9N Rng: 58W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 5302 ft

18. Distance to nearest property line: 501 ft 19. Distance to nearest well permitted/completed in the same formation: 5280 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		640	All

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See the attached lease description. A spacing application was filed on November 22, 2010.

25. Distance to Nearest Mineral Lease Line: 600 ft 26. Total Acres in Lease: 3598

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: Backfill and cover

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Line Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	13	42		60	50	60	0
SURF	13+1/2	9+5/8	36		800	420	800	0
1ST	8+3/4	7	23		5,907	630	5,907	0
1ST LINER	6	4+1/2	11.6	5157	10,137	310	10,137	5,157

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments _____

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jennifer Yu

Title: Regulatory Administrator Date: _____ Email: jennifer_yu@eogresources.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER	Permit Number: _____	Expiration Date: _____
05	CONDITIONS OF APPROVAL, IF ANY:	

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

--

Attachment Check List

Att Doc Num	Name
400117770	PLAT
400117771	TOPO MAP
400117772	LEGAL/LEASE DESCRIPTION
400117774	DRILLING PLAN
400117775	DEVIATED DRILLING PLAN

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)