

FORM  
5A

Rev  
02/08

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400093957

**COMPLETED INTERVAL REPORT**

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120 4. Contact Name: Cindy Vue  
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6832  
3. Address: P O BOX 173779 Fax: (720) 929-7832  
City: DENVER State: CO Zip: 80217-37

5. API Number 05-123-21687-00 6. County: WELD  
7. Well Name: XCEL Well Number: 14-3  
8. Location: QtrQtr: SWSE Section: 3 Township: 3N Range: 67W Meridian: 6  
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: <u>NIOBRARA-CODELL</u>	Status: <u>PRODUCING</u>
Treatment Date: <u>08/24/2010</u>	Date of First Production this formation: <u>09/07/2010</u>
Perforations Top: <u>6932</u> Bottom: <u>7236</u>	No. Holes: <u>114</u> Hole size: <u>38/100</u>
Provide a brief summary of the formation treatment: Open Hole: <input type="checkbox"/>	
<div>NBRR Perf 6932-7014 Holes 62 Size 0.42 CODL Perf 7216-7236 Holes 52 Size 0.38 Reperf NBRR 6932-7012 Holes 56 Size 0.42 Refrac NBRR w/ 250 gal 15% HCl &amp; 172,586 gal Super Z LpH Hybrid &amp; 250,160# 20/40 sand &amp; 4,000# SB Excel. Reperf CODL 7216-7236 Holes 40 Size 0.38. Refrac CODL w/ 124,799 gal Super Z LpH &amp; 261,020# 20/40 sand &amp; 4,000# SB Excel.</div>	
This formation is commingled with another formation: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
<b>Test Information:</b>	
Date: <u>09/11/2010</u> Hours: <u>24</u> Bbls oil: <u>14</u> Mcf Gas: <u>138</u> Bbls H2O: <u>0</u>	
Calculated 24 hour rate: Bbls oil: <u>14</u> Mcf Gas: <u>138</u> Bbls H2O: <u>0</u> GOR: <u>9857</u>	
Test Method: <u>FLOWING</u> Casing PSI: <u>1256</u> Tubing PSI: <u>827</u> Choke Size: <u>14/64</u>	
Gas Disposition: <u>SOLD</u> Gas Type: <u>WET</u> BTU Gas: <u>1371</u> API Gravity Oil: <u>52</u>	
Tubing Size: <u>2 + 3/8</u> Tubing Setting Depth: <u>7192</u> Tbg setting date: <u>08/30/2010</u> Packer Depth: <u></u>	
Reason for Non-Production: <div></div>	
Date formation Abandoned: <u></u> Squeeze: <input type="checkbox"/> Yes <input type="checkbox"/> No If yes, number of sacks cmt <u></u>	
Bridge Plug Depth: <u></u> Sacks cement on top: <u></u>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Cindy Vue

Title: Regulatory Analyst II

Date: 9/20/2010

Email Cindy.Vue@anadarko.com  
:

Based on the information provided herein, this Completed Interval Report (Form 5A) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin

Director of COGCC

Date: 12/23/2010

**Attachment Check List**

Att Doc Num	Name
400093957	FORM 5A SUBMITTED

Total Attach: 1 Files

**General Comments**

**User Group**      **Comment**      **Comment Date**

--	--	--

Total: 0 comment(s)