



Andrews, David

From: GJRig01@oxy.com
Sent: Sunday, December 26, 2010 1:41 AM
To: Andrews, David
Cc: Brad_Ahlquist@Oxy.com; Victor_Guerra@oxy.com; Nikolai_Amortegui@oxy.com; simonjrben@aol.com; Linda_Kuether@oxy.com; Paul_Townsend@oxy.com; sanchez49@aol.com
Subject: SURFACE CEMENT CC697-08-31A

WELL CC697-08-31A
SHOE SET AT 2712'
API-05045183520000

TESTED LINES TO 3500 PSI.
PUMPED 20 BBLS FRESH WATER 20 BBLS OF GEL SPACER 20 BBLS OF FRESH WATER.
CEMENTED 9.625" SURFACE CASING WITH:
1,075 SACKS OF LEAD - 446 BBLS OF 12.3 PPG - 2.33 CU. FT/SK VERSACEM LEAD WITH TUFF FIBER.
160 SACKS OF TAIL - 59 BBLS OF 12.8 PPG - 2.07 CU. FT/SK VERSACEM TAIL. LOST RETURNS 130
BBLS INTO LEAD WHILE PUMPING LEAD AND TAIL.
DISPLACED WITH 205 BBLS FRESH WATER AT 6-4-2 BPM. OBSERVED NO CEMENT RETURNS AT SURFACE.
50% EXCESS ON LEAD AND TAIL
OBSERVED 380 PSI LIFT PRESSURE AT 2 BPM. BUMPED PLUG WITH 900 PSI. FLOATS HELD.
FLUSHED PARASITE LINE WITH 10 BBLS SUGAR WATER - HAD RETURNS AFTER 6.5 BBLS - CIRCULATED AT
470 PSI @ 2.0 BPM.
TEST CASING TO 1500 PSI, PRESSURE DROPPED TO 900 PSI CHECKED HALLIBURTON EQUIPMENT RE-TEST
PRESSURE STILL DROPPED, WHILE TESTING BOPE, A CASING TEST WILL BE PERFORMED "NO TEST".
RIG DOWN HALLIBURTON.

TOPPED OUT OFF LINE WITH 25 BBLS CEMENT WITH RETURNS TO SURFACE. WAITED 10 MINS. PUMPED 6
BBLS MORE WITH RETURNS TO SURFACE AND NO DROP.

THANK YOU,

D.S.M
H&P 330
1-281-436-6424