

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refilling ☐
Sidetrack ☐

Document Number:

400094198

Plugging Bond Surety

20010124

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: CHERYL LIGHT Phone: (720)929-6461 Fax: (720)929-7461
Email: CHERYL.LIGHT@ANADARKO.COM

7. Well Name: SEKICH Well Number: 14-19

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7987

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 19 Twp: 3N Rng: 67W Meridian: 6

Latitude: 40.204984 Longitude: -104.930925

Footage at Surface: 235 feet FNL/FSL FSL 2140 feet FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4907 13. County: WELD

14. GPS Data:

Date of Measurement: 06/18/2010 PDOP Reading: 2.3 Instrument Operator's Name: CHRIS PEARSON

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 660 FSL 1980 FWL FWL Bottom Hole: FNL/FSL 660 FSL 1980 FWL FWL
Sec: 19 Twp: 3N Rng: 67W Sec: 19 Twp: 3N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 222 ft

18. Distance to nearest property line: 240 ft 19. Distance to nearest well permitted/completed in the same formation: 961 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J-SAND	JSND	232	320	W2
NIOBRARA-CODELL	NB-CD	407	80	S2SW4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Sec 19 T3N R67W: SW4

25. Distance to Nearest Mineral Lease Line: 553 ft 26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Line Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24		750	525	750	
1ST	7+7/8	4+1/2	11.6		7,987	200	7,987	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED . Kerr-McGee Oil & Gas Onshore LP requests approval of a Rule 318Aa and Rule 318Ac exception location: Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location. Waivers are attached.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CHERYL LIGHT

Title: SEN. REGULATORY ANALYST Date: 12/6/2010 Email: DJREGULATORY@ANADARK

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 12/28/2010

API NUMBER

05 123 32771 00

Permit Number: _____ Expiration Date: 12/27/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Bo Brown at 970-397-4124 or e-mail at bo.brown@state.co.us.
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
1770675	SURFACE CASING CHECK
400094198	FORM 2 SUBMITTED
400112646	DEVIATED DRILLING PLAN
400112647	30 DAY NOTICE LETTER
400112648	PLAT
400112649	SURFACE AGRMT/SURETY
400112650	TOPO MAP
400112651	EXCEPTION LOC WAIVERS
400112652	EXCEPTION LOC REQUEST
400112662	OIL & GAS LEASE

Total Attach: 10 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)