




Well Name:	Battlement Mesa 34-43B
Legal Description:	NWSW Sec35 T7S R95W
COGCC #	400036078
API#	05 045 19854 00
Rig Name and Number:	H&P 322
Noble Energy Supervisor:	Charles Collver
Phone number at rig:	832-518-2497



This notice, sent on 12/28/2010 is to inform you that we intend
to run: 9 5/8" 36# LTC casing and cement same
within the next 24 hours.

Phone notification made to _____ at _____
on _____

Additionally:

Drilled 14-3/4" hole t/3338', ran 9-5/8" ,36# , LTC set @ 3328.10'
cemented w/ lead 1089 sacks, 12.3# , 2.32 YP
tail 194 sacks 12.6# , 2.14 YP *625 psi lift pressure*
Top Job Ran 1" T/240' Pumped 150 Sacks 15.8#, 1.15YP
2nd Top Job Ran 1" T/85' Pumped 75 Sacks 15.8#, 1.15 YP
5 bbl cement to surface

D.A.