

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☒

Sidetrack ☐

Document Number:

400111285

Plugging Bond Surety

20090025

3. Name of Operator: AUGUSTUS ENERGY PARTNERS LLC

4. COGCC Operator Number: 10275

5. Address: P O BOX 250

City: WRAY State: CO Zip: 80758

6. Contact Name: Loni Davis Phone: (970)332-3585 Fax: (970)332-3587

Email: ldavis@augustusenergy.com

7. Well Name: Brown Well Number: 34-03 1N47W

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 2900

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 3 Twp: 1N Rng: 47W Meridian: 6

Latitude: 40.078600 Longitude: -102.611540

Footage at Surface: 1149 feet FNL/FSL 1604 feet FEL/FWL FEL

11. Field Name: Schramm Field Number: 76825

12. Ground Elevation: 4034 13. County: YUMA

14. GPS Data:

Date of Measurement: 07/08/2010 PDOP Reading: 2.8 Instrument Operator's Name: Neal McCormick

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1149 ft

18. Distance to nearest property line: 1080 ft 19. Distance to nearest well permitted/completed in the same formation: 906 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	329-5	160	SE/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: 20090026

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
1N47W, Sec 3: S2

25. Distance to Nearest Mineral Lease Line: 1149 ft 26. Total Acres in Lease: 320

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Line Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	9+7/8	7	20		500	200	500	0
1ST	6+1/4	4+1/2	10.5		2,900	75	2,900	2,100

32. BOP Equipment Type: ☐ Annular Preventer ☐ Double Ram ☐ Rotating Head ☒ None

33. Comments No Conductor Casing will be used. This location was abandoned on Berry Petroleum's behalf, but Augustus Energy purchased Berry Petroleum 04/01/09 and Augustus would like to refile this location using the existing API #05-125-11430-00. A change of operator has also been submitted (3/05/10) changing the location from Berry to Augustus. All conditions remain the same.

34. Location ID: 311037

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Loni J. Davis

Title: Oper Acctg & Reg Spec Date: 12/1/2010 Email: ldavis@augustusenergy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 1/3/2011

API NUMBER

05 125 11430 00

Permit Number: _____ Expiration Date: 1/2/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hr notice of spud to Colby Horton at 970-867-2517 or e-mail at colby.horton@state.co.us.
- 2) Set surface casing at least 50' into Pierre Shale for aquifer coverage, (500' minimum - as proposed). Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
- 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 4) If dry hole, set 35 sks cement 50' above Niobrara top, 35 sks cement ½ out, ½ in surface casing, 10 sks cement at top of surface casing, cut casing 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole.

Attachment Check List

Att Doc Num	Name
400111285	FORM 2 SUBMITTED
400111288	30 DAY NOTICE LETTER
400111289	PLAT
400111290	TOPO MAP

Total Attach: 4 Files

General Comments

User Group	Comment	Comment Date
Permit	PERMITTING PASSED- JLV	12/9/2010 2:19:13 PM

Total: 1 comment(s)

BMP

Type	Comment

Total: 0 comment(s)